NAME OF WORK:- Extension and Additional Works to Parking Lot at 16th A Main and 16th B Cross Roads in Ward No-04

# Modified Estimation

**BRUHAT BANGALORE MAHANAGARA PALIKE**

**Name of Work: Extension and Additional Works to Parking Lot at 16th A main and 16thB Cross Roads in ward No 04**

**MODIFIED ESTIMATE**

| Chainage | | Description of Item | Unit | No | Length | Breadth | | | Depth | Qty | Rate | Amount |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| From | To | | | | | B1 | B2 | Avg | | | | |
| 1 | | Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. and as per the directions of the Engineer-in-charge of the work | | | | | | | | | | |
| | | parking Lot | | | | | | | | | | |
| | | Temple Surrounding | | | | | | | | | | |
| | | East Side | | | | | | | | | | |
| 0 | 5.55 | | Cum | 1 | 5.55 | 0.90 | 0.90 | 0.90 | 1.05 | 5.24 | | |
| 5.55 | 11.35 | No Work | Cum | 1 | 0.00 | 0.90 | 0.90 | 0.90 | 1.05 | 0.00 | | |
| | | | | | | | | | | | | |
| | | South Side | | | | | | | | | | |
| 0 | 15 | | Cum | 1 | 15.00 | 0.90 | 0.90 | 0.90 | 1.05 | 14.18 | | |
| 15 | 30 | | Cum | 1 | 15.00 | 0.90 | 0.90 | 0.90 | 1.05 | 14.18 | | |
| 30 | 35.2 | | Cum | 1 | 5.20 | 0.90 | 0.90 | 0.90 | 1.05 | 4.91 | | |
| | | | | | | | | | | | | |
| | | North Side | | | | | | | | | | |
| 0 | 7.9 | No Work | Cum | 1 | 0.00 | 0.90 | 0.90 | 0.90 | 1.05 | 0.00 | | |
| 7.9 | 21.2 | | Cum | 1 | 13.30 | 0.90 | 0.90 | 0.90 | 1.05 | 12.57 | | |
| 21.2 | 35 | No Work | Cum | 1 | 0.00 | 0.90 | 0.90 | 0.90 | 1.05 | 0.00 | | |
| | | | | | | | | | | | | |
| | | Between Car Parking And Bike Parking Lot Near Temple Side | | | | | | | | | | |
| 0 | 9.03 | | Cum | 1 | 9.03 | 0.90 | 0.90 | 0.90 | 1.05 | 8.53 | | |
| | | | | | | | | | | | | |
| | | Between Car Parking And Bike Parking Lot Near Toilet | | | | | | | | | | |
| 0 | 9.3 | | Cum | 1 | 9.30 | 0.90 | 0.90 | 0.90 | 1.05 | 8.79 | | |
| | | | | | | | | | | | | |
| | | EXTRA | | | | | | | | | | |
| | | Parking Lot Near Public Toilet | | | | | | | | | | |
| | | South Side | | | | | | | | | | |
| 0 | 15 | | Cum | 1 | 15.00 | 0.90 | 0.90 | 0.90 | 1.05 | 14.18 | | |
| 15 | 22.9 | | Cum | 1 | 7.90 | 0.90 | 0.90 | 0.90 | 1.05 | 7.47 | | |
| | | | | | | | | | | | | |
| | | West Side | | | | | | | | | | |
| 0 | 14.05 | Arch Portion | Cum | 1 | 14.05 | 0.90 | 0.90 | 0.90 | 1.05 | 13.28 | | |
| | | | | | | | | | | | | |
| | | North Side | | | | | | | | | | |
| 0 | 12.15 | | Cum | 1 | 12.15 | 0.90 | 0.90 | 0.90 | 1.05 | 11.48 | | |
| | | | | | | | | | | | | |
| | | 16th 'B' Cross Road Near Bus Stand | | | | | | | | | | |
| | | South Side | | | | | | | | | | |
| 0 | 11.1 | | Cum | 1 | 11.10 | 0.90 | 0.90 | 0.90 | 1.05 | 10.49 | | |
| | | | | | | | | | | | | |
| | | West Side | | | | | | | | | | |
| 0 | 15 | | Cum | 1 | 15.00 | 0.90 | 0.90 | 0.90 | 1.05 | 14.18 | | |
| 15 | 30 | | Cum | 1 | 15.00 | 0.90 | 0.90 | 0.90 | 1.05 | 14.18 | | |
| 30 | 37.6 | | Cum | 1 | 7.60 | 0.90 | 0.90 | 0.90 | 1.05 | 7.18 | | |
| | | | | | | | | | | | | |
| | | 16th B Cross Road | | | | | | | | | | |
| | | Service Road West Side | | | | | | | | | | |
| 0 | 15 | | Cum | 1 | 15.00 | 0.90 | 0.90 | 0.90 | 1.05 | 14.18 | | |
| 15 | 30 | | Cum | 1 | 15.00 | 0.90 | 0.90 | 0.90 | 1.05 | 14.18 | | |
| 30 | 45 | | Cum | 1 | 15.00 | 0.90 | 0.90 | 0.90 | 1.05 | 14.18 | | |
| 45 | 60 | | Cum | 1 | 15.00 | 0.90 | 0.90 | 0.90 | 1.05 | 14.18 | | |

| Chainage | | Description of Item | Unit | No | Length | Breadth | | | Depth | Qty | Rate | Amount |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| From | To | | | | | B1 | B2 | Avg | | | | |
| 60 | 75 | | Cum | 1 | 15.00 | 0.90 | 0.90 | 0.90 | 1.05 | 14.18 | | |
| 75 | 90 | | Cum | 1 | 15.00 | 0.90 | 0.90 | 0.90 | 1.05 | 14.18 | | |
| 90 | 105 | | Cum | 1 | 15.00 | 0.90 | 0.90 | 0.90 | 1.05 | 14.18 | | |
| 105 | 107.1 | | Cum | 1 | 2.10 | 0.90 | 0.90 | 0.90 | 1.05 | 1.98 | | |
| | | | | | | | | | | | | |
| | | North Side | | | | | | | | | | |
| 0 | 5.4 | | Cum | 1 | 5.40 | 0.90 | 0.90 | 0.90 | 1.05 | 5.10 | | |
| | | | | | | | | | | | | |
| | | South Side | | | | | | | | | | |
| 0 | 5.5 | | Cum | 1 | 5.50 | 0.90 | 0.90 | 0.90 | 1.05 | 5.20 | | |
| | | | | | | | | | | | | |
| | | East Side | | | | | | | | | | |
| 0 | 2.5 | Gate | Cum | 1 | 0.00 | 0.90 | 0.90 | 0.90 | 1.05 | 0.00 | | |
| 2.5 | 17.5 | | Cum | 1 | 15.00 | 0.90 | 0.90 | 0.90 | 1.05 | 14.18 | | |
| 17.5 | 32.5 | | Cum | 1 | 15.00 | 0.90 | 0.90 | 0.90 | 1.05 | 14.18 | | |
| 32.5 | 47.5 | | Cum | 1 | 15.00 | 0.90 | 0.90 | 0.90 | 1.05 | 14.18 | | |
| 47.5 | 62.5 | | Cum | 1 | 15.00 | 0.90 | 0.90 | 0.90 | 1.05 | 14.18 | | |
| 62.5 | 77.5 | | Cum | 1 | 15.00 | 0.90 | 0.90 | 0.90 | 1.05 | 14.18 | | |
| 77.5 | 92.5 | | Cum | 1 | 15.00 | 0.90 | 0.90 | 0.90 | 1.05 | 14.18 | | |
| 92.5 | 103.5 | | Cum | 1 | 11.00 | 0.90 | 0.90 | 0.90 | 1.05 | 10.40 | | |
| 103.5 | 105.7 | Gate | Cum | 1 | 0.00 | 0.90 | 0.90 | 0.90 | 1.05 | 0.00 | | |
| | | | | | | | | | | | | |
| | | Judicial Layout | | | | | | | | | | |
| | | South Side | | | | | | | | | | |
| 0 | 6.5 | | Cum | 1 | 6.50 | 0.90 | 0.90 | 0.90 | 1.05 | 6.14 | | |
| | | | | | | | | | | | | |
| | | West Side | | | | | | | | | | |
| 0 | 15 | | Cum | 1 | 15.00 | 0.90 | 0.90 | 0.90 | 1.05 | 14.18 | | |
| 15 | 25.65 | | Cum | 1 | 10.65 | 0.90 | 0.90 | 0.90 | 1.05 | 10.06 | | |
| | | | | | | | | | **Total** | **398.16** | | |
| | | | | | | | | | **Tender Quantity** | **177.70** | | |
| | | | | | | | | | **Quantity Upto 125%** | **222.12** | **405.50** | **90071.00** |
| | | | | | | | | | **Quantity Above 125%** | **176.03** | **405.69** | **71416.00** |
| **2** | | Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications. and as per the directions of the Engineer-in-charge of the work | | | | | | | | | | |
| | | 16th 'B' Cross Road Near Bus Stand | | | | | | | | | | |
| | | East Side | | | | | | | | | | |
| 0 | 15 | | Cum | 1 | 15 | 0.50 | 0.50 | 0.50 | 0.55 | 4.13 | | |
| 15 | 30 | | Cum | 1 | 15 | 0.50 | 0.50 | 0.50 | 0.55 | 4.13 | | |
| 30 | 36.9 | | Cum | 1 | 6.9 | 0.50 | 0.50 | 0.50 | 0.55 | 1.90 | | |
| | | | | | | | | | **Total** | **10.15** | **390.10** | **3959.00** |
| | | | | | | | | | **Tender Quantity** | **10.89** | | |
| **3** | | Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually ( other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables ) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface levelled and neatly dressed, disposed earth to be levelled after breaking of clods and neatly dressed as per specifications. and as per the directions of the Engineer-in-charge of the work | | | | | | | | | | |
| | | 16th 'B' Cross Road | | | | | | | | | | |
| 0 | 15 | | Sqm | 1 | 15.00 | 5.95 | 5.95 | 5.95 | 0.30 | 26.78 | | |
| 15 | 30 | | Sqm | 1 | 15.00 | 5.95 | 5.95 | 5.95 | 0.30 | 26.78 | | |
| 30 | 37.6 | | Sqm | 1 | 7.60 | 5.95 | 5.95 | 5.95 | 0.30 | 13.57 | | |
| | | | | | | | | | | | | |
| | | Deduction | | | | | | | | | | |
| | | | Sqm | -1 | 2.10 | 1.90 | 1.90 | 1.90 | 0.30 | -1.20 | | |
| | | | | | | | | | **Total** | **65.92** | **349.93** | **23068.00** |
| | | | | | | | | | **Tender Quantity** | **70.69** | | |

| Chainage | | Description of Item | Unit | No | Length | Breadth | | | Depth | Qty | Rate | Amount |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| From | To | | | | | B1 | B2 | Avg | | | | |
| 4 | | Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications. and as per the directions of the Engineer-in-charge of the work | | | | | | | | | | |
| | | parking Lot | | | | | | | | | | |
| | | Temple Surrounding | | | | | | | | | | |
| | | East Side | | | | | | | | | | |
| 0 | 5.55 | | Cum | 1 | 5.55 | 0.90 | 0.90 | 0.90 | 0.15 | 0.75 | | |
| 5.55 | 11.35 | No Work | Cum | 1 | 0.00 | 0.90 | 0.90 | 0.90 | 0.15 | 0.00 | | |
| | | | | | | | | | | | | |
| | | South Side | | | | | | | | | | |
| 0 | 15 | | Cum | 1 | 15.00 | 0.90 | 0.90 | 0.90 | 0.15 | 2.03 | | |
| 15 | 30 | | Cum | 1 | 15.00 | 0.90 | 0.90 | 0.90 | 0.15 | 2.03 | | |
| 30 | 35.2 | | Cum | 1 | 5.20 | 0.90 | 0.90 | 0.90 | 0.15 | 0.70 | | |
| | | | | | | | | | | | | |
| | | North Side | | | | | | | | | | |
| 0 | 7.9 | No Work | Cum | 1 | 0.00 | 0.90 | 0.90 | 0.90 | 0.15 | 0.00 | | |
| 7.9 | 21.2 | | Cum | 1 | 13.30 | 0.90 | 0.90 | 0.90 | 0.15 | 1.80 | | |
| 21.2 | 35 | No Work | Cum | 1 | 0.00 | 0.90 | 0.90 | 0.90 | 0.15 | 0.00 | | |
| | | | | | | | | | | | | |
| | | Between Car Parking And Bike Parking Lot Near Temple Side | | | | | | | | | | |
| 0 | 9.03 | | Cum | 1 | 9.03 | 0.90 | 0.90 | 0.90 | 0.15 | 1.22 | | |
| | | | | | | | | | | | | |
| | | Between Car Parking And Bike Parking Lot Near Toilet | | | | | | | | | | |
| 0 | 9.3 | | Cum | 1 | 9.30 | 0.90 | 0.90 | 0.90 | 0.15 | 1.26 | | |
| | | | | | | | | | | | | |
| | | EXTRA | | | | | | | | | | |
| | | Parking Lot Near Public Toilet | | | | | | | | | | |
| | | South Side | | | | | | | | | | |
| 0 | 15 | | Cum | 1 | 15.00 | 0.90 | 0.90 | 0.90 | 0.15 | 2.03 | | |
| 15 | 22.9 | | Cum | 1 | 7.90 | 0.90 | 0.90 | 0.90 | 0.15 | 1.07 | | |
| | | | | | | | | | | | | |
| | | West Side | | | | | | | | | | |
| 0 | 14.05 | Arch Portion | Cum | 1 | 14.05 | 0.90 | 0.90 | 0.90 | 0.15 | 1.90 | | |
| | | | | | | | | | | | | |
| | | North Side | | | | | | | | | | |
| 0 | 12.15 | | Cum | 1 | 12.15 | 0.90 | 0.90 | 0.90 | 0.15 | 1.64 | | |
| | | | | | | | | | | | | |
| | | 16th 'B' Cross Road Near Bus Stand | | | | | | | | | | |
| | | South Side | | | | | | | | | | |
| 0 | 11.1 | | Cum | 1 | 11.10 | 0.90 | 0.90 | 0.90 | 0.15 | 1.50 | | |
| | | | | | | | | | | | | |
| | | West Side | | | | | | | | | | |
| 0 | 15 | | Cum | 1 | 15.00 | 0.90 | 0.90 | 0.90 | 0.15 | 2.03 | | |
| 15 | 30 | | Cum | 1 | 15.00 | 0.90 | 0.90 | 0.90 | 0.15 | 2.03 | | |
| 30 | 37.6 | | Cum | 1 | 7.60 | 0.90 | 0.90 | 0.90 | 0.15 | 1.03 | | |
| | | | | | | | | | | | | |
| | | 16th B Cross Road | | | | | | | | | | |
| | | Service Road West Side | | | | | | | | | | |
| 0 | 15 | | Cum | 1 | 15.00 | 0.90 | 0.90 | 0.90 | 0.15 | 2.03 | | |
| 15 | 30 | | Cum | 1 | 15.00 | 0.90 | 0.90 | 0.90 | 0.15 | 2.03 | | |
| 30 | 45 | | Cum | 1 | 15.00 | 0.90 | 0.90 | 0.90 | 0.15 | 2.03 | | |
| 45 | 60 | | Cum | 1 | 15.00 | 0.90 | 0.90 | 0.90 | 0.15 | 2.03 | | |
| 60 | 75 | | Cum | 1 | 15.00 | 0.90 | 0.90 | 0.90 | 0.15 | 2.03 | | |
| 75 | 90 | | Cum | 1 | 15.00 | 0.90 | 0.90 | 0.90 | 0.15 | 2.03 | | |
| 90 | 105 | | Cum | 1 | 15.00 | 0.90 | 0.90 | 0.90 | 0.15 | 2.03 | | |
| 105 | 107.1 | | Cum | 1 | 2.10 | 0.90 | 0.90 | 0.90 | 0.15 | 0.28 | | |

| Chainage | | Description of Item | Unit | No | Length | Breadth | | | Depth | Qty | Rate | Amount |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| From | To | | | | | B1 | B2 | Avg | | | | |
| | | North Side | | | | | | | | | | |
| 0 | 5.4 | | Cum | 1 | 5.40 | 0.90 | 0.90 | 0.90 | 0.15 | 0.73 | | |
| | | South Side | | | | | | | | | | |
| 0 | 5.5 | | Cum | 1 | 5.50 | 0.90 | 0.90 | 0.90 | 0.15 | 0.74 | | |
| | | East Side | | | | | | | | | | |
| 0 | 2.5 | Gate | Cum | 1 | 0.00 | 0.90 | 0.90 | 0.90 | 0.15 | 0.00 | | |
| 2.5 | 17.5 | | Cum | 1 | 15.00 | 0.90 | 0.90 | 0.90 | 0.15 | 2.03 | | |
| 17.5 | 32.5 | | Cum | 1 | 15.00 | 0.90 | 0.90 | 0.90 | 0.15 | 2.03 | | |
| 32.5 | 47.5 | | Cum | 1 | 15.00 | 0.90 | 0.90 | 0.90 | 0.15 | 2.03 | | |
| 47.5 | 62.5 | | Cum | 1 | 15.00 | 0.90 | 0.90 | 0.90 | 0.15 | 2.03 | | |
| 62.5 | 77.5 | | Cum | 1 | 15.00 | 0.90 | 0.90 | 0.90 | 0.15 | 2.03 | | |
| 77.5 | 92.5 | | Cum | 1 | 15.00 | 0.90 | 0.90 | 0.90 | 0.15 | 2.03 | | |
| 92.5 | 103.5 | | Cum | 1 | 11.00 | 0.90 | 0.90 | 0.90 | 0.15 | 1.49 | | |
| 103.5 | 105.7 | Gate | Cum | 1 | 0.00 | 0.90 | 0.90 | 0.90 | 0.15 | 0.00 | | |
| | | Judicial Layout | | | | | | | | | | |
| | | South Side | | | | | | | | | | |
| 0 | 6.5 | | Cum | 1 | 6.50 | 0.90 | 0.90 | 0.90 | 0.15 | 0.88 | | |
| | | West Side | | | | | | | | | | |
| 0 | 15 | | Cum | 1 | 15.00 | 0.90 | 0.90 | 0.90 | 0.15 | 2.03 | | |
| 15 | 25.65 | | Cum | 1 | 10.65 | 0.90 | 0.90 | 0.90 | 0.15 | 1.44 | | |
| | | 16th 'B' Cross Road | | | | | | | | | | |
| 0 | 15 | | Cum | 1 | 15.00 | 5.95 | 5.95 | 5.95 | 0.15 | 13.39 | | |
| 15 | 30 | | Cum | 1 | 15.00 | 5.95 | 5.95 | 5.95 | 0.15 | 13.39 | | |
| 30 | 37.6 | | Cum | 1 | 7.60 | 5.95 | 5.95 | 5.95 | 0.15 | 6.78 | | |
| | | Judicial Layout | | | | | | | | | | |
| 0 | 2.65 | | Sqm | 1 | 2.65 | 6.40 | 6.40 | 6.40 | 0.15 | 2.54 | | |
| 2.65 | 17.65 | | Sqm | 1 | 15.00 | 4.90 | 4.90 | 4.90 | 0.15 | 11.03 | | |
| 17.65 | 23.65 | | Sqm | 1 | 6.00 | 4.90 | 4.90 | 4.90 | 0.15 | 4.41 | | |
| 23.65 | 25.45 | | Sqm | 1 | 1.80 | 6.00 | 6.00 | 6.00 | 0.15 | 1.62 | | |
| | | Deduction | | | | | | | | | | |
| | | | Cum | -1 | 2.10 | 1.90 | 1.90 | 1.90 | 0.15 | -0.60 | | |
| | | Door | Sqm | -1 | 2.54 | 0.87 | 0.87 | 0.87 | 0.15 | -0.33 | | |
| | | Borewell | Sqm | -1 | 1.20 | 0.90 | 0.90 | 0.90 | 0.15 | -0.16 | | |
| | | Chamber | Sqm | -2 | 1.00 | 0.70 | 0.70 | 0.70 | 0.15 | -0.21 | | |
| | | **Total** | | | | | | | | 108.73 | | |
| | | | | | | | | | **Tender Quantity** | 73.24 | | |
| | | | | | | | | | **Quantity Upto 125%** | 91.55 | 5772.66 | 528478.00 |
| | | | | | | | | | **Quantity Above 125%** | 17.19 | 6282.46 | 107973.00 |
| 5 | | Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications, and as per the directions of the Engineer-in-charge of the work | | | | | | | | | | |
| | | parking Lot | | | | | | | | | | |
| | | Temple Surrounding | | | | | | | | | | |
| | | East Side | | | | | | | | | | |
| 0 | 5.55 | | Cum | 1 | 5.55 | 0.90 | 0.90 | 0.90 | 0.90 | 4.50 | | |
| 5.55 | 11.35 | No Work | Cum | 1 | 0.00 | 0.90 | 0.90 | 0.90 | 0.90 | 0.00 | | |
| | | South Side | | | | | | | | | | |
| 0 | 15 | | Cum | 1 | 15.00 | 0.90 | 0.90 | 0.90 | 0.90 | 12.15 | | |
| 15 | 30 | | Cum | 1 | 15.00 | 0.90 | 0.90 | 0.90 | 0.90 | 12.15 | | |
| 30 | 35.2 | | Cum | 1 | 5.20 | 0.90 | 0.90 | 0.90 | 0.90 | 4.21 | | |
| | | North Side | | | | | | | | | | |
| 0 | 7.9 | No Work | Cum | 1 | 0.00 | 0.90 | 0.90 | 0.90 | 0.90 | 0.00 | | |
| 7.9 | 21.2 | | Cum | 1 | 13.30 | 0.90 | 0.90 | 0.90 | 0.90 | 10.77 | | |

| Chainage | | Description of Item | Unit | No | Length | Breadth | | | Depth | Qty | Rate | Amount |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| From | To | | | | | B1 | B2 | Avg | | | | |
| 21.2 | 35 | No Work | Cum | 1 | 0.00 | 0.90 | 0.90 | 0.90 | 0.90 | 0.00 | | |
| | | Between Car Parking And Bike Parking Lot Near Temple Side | | | | | | | | | | |
| 0 | 9.03 | | Cum | 1 | 9.03 | 0.90 | 0.90 | 0.90 | 0.90 | 7.31 | | |
| | | Between Car Parking And Bike Parking Lot Near Toilet | | | | | | | | | | |
| 0 | 9.3 | | Cum | 1 | 9.30 | 0.90 | 0.90 | 0.90 | 0.90 | 7.53 | | |
| | | EXTRA | | | | | | | | | | |
| | | Parking Lot Near Public Toilet | | | | | | | | | | |
| | | South Side | | | | | | | | | | |
| 0 | 15 | | Cum | 1 | 15.00 | 0.90 | 0.90 | 0.90 | 0.90 | 12.15 | | |
| 15 | 22.9 | | Cum | 1 | 7.90 | 0.90 | 0.90 | 0.90 | 0.90 | 6.40 | | |
| | | West Side | | | | | | | | | | |
| 0 | 14.05 | Arch Portion | Cum | 1 | 14.05 | 0.90 | 0.90 | 0.90 | 0.90 | 11.38 | | |
| | | North Side | | | | | | | | | | |
| 0 | 12.15 | | Cum | 1 | 12.15 | 0.90 | 0.90 | 0.90 | 0.90 | 9.84 | | |
| | | 16th 'B' Cross Road Near Bus Stand | | | | | | | | | | |
| | | South Side | | | | | | | | | | |
| 0 | 11.1 | | Cum | 1 | 11.10 | 0.90 | 0.90 | 0.90 | 0.90 | 8.99 | | |
| | | West Side | | | | | | | | | | |
| 0 | 15 | | Cum | 1 | 15.00 | 0.90 | 0.90 | 0.90 | 0.90 | 12.15 | | |
| 15 | 30 | | Cum | 1 | 15.00 | 0.90 | 0.90 | 0.90 | 0.90 | 12.15 | | |
| 30 | 37.6 | | Cum | 1 | 7.60 | 0.90 | 0.90 | 0.90 | 0.90 | 6.16 | | |
| | | 16th B Cross Road Service Road West Side | | | | | | | | | | |
| 0 | 15 | | Cum | 1 | 15.00 | 0.90 | 0.90 | 0.90 | 0.90 | 12.15 | | |
| 15 | 30 | | Cum | 1 | 15.00 | 0.90 | 0.90 | 0.90 | 0.90 | 12.15 | | |
| 30 | 45 | | Cum | 1 | 15.00 | 0.90 | 0.90 | 0.90 | 0.90 | 12.15 | | |
| 45 | 60 | | Cum | 1 | 15.00 | 0.90 | 0.90 | 0.90 | 0.90 | 12.15 | | |
| 60 | 75 | | Cum | 1 | 15.00 | 0.90 | 0.90 | 0.90 | 0.90 | 12.15 | | |
| 75 | 90 | | Cum | 1 | 15.00 | 0.90 | 0.90 | 0.90 | 0.90 | 12.15 | | |
| 90 | 105 | | Cum | 1 | 15.00 | 0.90 | 0.90 | 0.90 | 0.90 | 12.15 | | |
| 105 | 107.1 | | Cum | 1 | 2.10 | 0.90 | 0.90 | 0.90 | 0.90 | 1.70 | | |
| | | North Side | | | | | | | | | | |
| 0 | 5.4 | | Cum | 1 | 5.40 | 0.90 | 0.90 | 0.90 | 0.90 | 4.37 | | |
| | | South Side | | | | | | | | | | |
| 0 | 5.5 | | Cum | 1 | 5.50 | 0.90 | 0.90 | 0.90 | 0.90 | 4.46 | | |
| | | East Side | | | | | | | | | | |
| 0 | 2.5 | Gate | Cum | 1 | 0.00 | 0.90 | 0.90 | 0.90 | 0.90 | 0.00 | | |
| 2.5 | 17.5 | | Cum | 1 | 15.00 | 0.90 | 0.90 | 0.90 | 0.90 | 12.15 | | |
| 17.5 | 32.5 | | Cum | 1 | 15.00 | 0.90 | 0.90 | 0.90 | 0.90 | 12.15 | | |
| 32.5 | 47.5 | | Cum | 1 | 15.00 | 0.90 | 0.90 | 0.90 | 0.90 | 12.15 | | |
| 47.5 | 62.5 | | Cum | 1 | 15.00 | 0.90 | 0.90 | 0.90 | 0.90 | 12.15 | | |
| 62.5 | 77.5 | | Cum | 1 | 15.00 | 0.90 | 0.90 | 0.90 | 0.90 | 12.15 | | |
| 77.5 | 92.5 | | Cum | 1 | 15.00 | 0.90 | 0.90 | 0.90 | 0.90 | 12.15 | | |
| 92.5 | 103.5 | | Cum | 1 | 11.00 | 0.90 | 0.90 | 0.90 | 0.90 | 12.15 | | |
| 103.5 | 105.7 | Gate | Cum | 1 | 0.00 | 0.90 | 0.90 | 0.90 | 0.90 | 8.91 | | |
| | | | | | | | | | | 0.00 | | |

| Chainage From | Chainage To | Description of Item | Unit | No | Length | Breadth B1 | Breadth B2 | Breadth Avg | Depth | Qty | Rate | Amount |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | Judicial Layout | | | | | | | | | | |
| | | South Side | | | | | | | | | | |
| 0 | 6.5 | | Cum | 1 | 6.50 | 0.90 | 0.90 | 0.90 | 0.90 | 5.27 | | |
| | | West Side | | | | | | | | | | |
| 0 | 15 | | Cum | 1 | 15.00 | 0.90 | 0.90 | 0.90 | 0.90 | 12.15 | | |
| 15 | 25.65 | | Cum | 1 | 10.65 | 0.90 | 0.90 | 0.90 | 0.90 | 8.63 | | |
| | | | | | | | | | Total | 341.28 | | |
| | | | | | | | | | Tender Quantity | 138.97 | | |
| | | | | | | | | | Quantity Upto 125% | 173.71 | 5108.04 | 887325.00 |
| | | | | | | | | | Quantity Above 125% | 167.57 | 5110.48 | 856343.00 |
| 6 | | Providing and constructing granite / trap / basalt size stone masonry in superstructure with cement mortar 1:4 , edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, scaffolding, curing complete as per specifications. and as per the directions of the Engineer-in-charge of the work | | | | | | | | | | |
| | | parking Lot | | | | | | | | | | |
| | | Temple Surrounding | | | | | | | | | | |
| | | East Side | | | | | | | | | | |
| 0 | 5.55 | | Cum | 1 | 5.55 | 0.45 | 0.45 | 0.45 | 0.40 | 1.00 | | |
| 5.55 | 11.35 | No Work | Cum | 1 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | | |
| | | South Side | | | | | | | | | | |
| 0 | 15 | | Cum | 1 | 15.00 | 0.45 | 0.47 | 0.46 | 0.45 | 3.11 | | |
| 15 | 18 | | Cum | 1 | 3.00 | 0.47 | 0.45 | 0.46 | 0.45 | 0.62 | | |
| 18 | 19.2 | Gate | Cum | 1 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | | |
| 19.2 | 31.6 | | Cum | 1 | 12.40 | 0.47 | 0.50 | 0.49 | 0.40 | 2.41 | | |
| 31.6 | 33 | Gate | Cum | 1 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | | |
| 33 | 35.2 | | Cum | 1 | 2.20 | 0.50 | 0.51 | 0.51 | 0.40 | 0.44 | | |
| | | North Side | | | | | | | | | | |
| 0 | 7.9 | No Work | Cum | 1 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | | |
| 7.9 | 21.2 | | Cum | 1 | 13.30 | 0.45 | 0.45 | 0.45 | 0.65 | 3.89 | | |
| 21.2 | 35 | No Work | Cum | 1 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | | |
| | | Between Car Parking And Bike Parking Lot Near Temple Side | | | | | | | | | | |
| 0 | 9.03 | | Cum | 1 | 9.03 | 0.45 | 0.45 | 0.45 | 0.45 | 1.83 | | |
| | | Between Car Parking And Bike Parking Lot Near Toilet | | | | | | | | | | |
| 0 | 9.3 | | Cum | 1 | 9.30 | 0.45 | 0.45 | 0.45 | 0.45 | 1.88 | | |
| | | Parking Lot Near Public Toilet | | | | | | | | | | |
| | | South Side | | | | | | | | | | |
| 0 | 1.9 | | Cum | 1 | 1.90 | 0.50 | 0.50 | 0.50 | 0.50 | 0.48 | | |
| 1.9 | 3.7 | Gate | Cum | 1 | 0.00 | 0.50 | 0.50 | 0.50 | 0.50 | 0.00 | | |
| 3.7 | 22.9 | | Cum | 1 | 19.20 | 0.50 | 0.50 | 0.50 | 0.50 | 4.80 | | |
| | | West Side | | | | | | | | | | |
| 0 | 14.05 | Arch Portion | Cum | 1 | 14.05 | 0.50 | 0.50 | 0.50 | 0.50 | 3.51 | | |
| | | North Side | | | | | | | | | | |
| 0 | 12.15 | | Cum | 1 | 12.15 | 0.50 | 0.50 | 0.50 | 0.50 | 3.04 | | |
| | | 16th 'B' Cross Road Near Bus Stand | | | | | | | | | | |
| | | South Side | | | | | | | | | | |
| 0 | 11.1 | | Cum | 1 | 11.10 | 0.50 | 0.50 | 0.50 | 0.50 | 2.78 | | |
| | | West Side | | | | | | | | | | |

| Chainage | | Description of Item | Unit | No | Length | Breadth | | | Depth | Qty | Rate | Amount |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| From | To | | | | | B1 | B2 | Avg | | | | |
| 0 | 15 | | Cum | 1 | 15.00 | 0.50 | 0.50 | 0.50 | 0.50 | 3.75 | | |
| 15 | 30 | | Cum | 1 | 15.00 | 0.50 | 0.50 | 0.50 | 0.50 | 3.75 | | |
| 30 | 37.6 | | Cum | 1 | 7.60 | 0.50 | 0.50 | 0.50 | 0.50 | 1.90 | | |
| | | | | | | | | | | | | |
| | | 16th B Cross Road | | | | | | | | | | |
| | | Service Road West Side | | | | | | | | | | |
| 0 | 15 | | Cum | 1 | 15.00 | 0.50 | 0.50 | 0.50 | 0.50 | 3.75 | | |
| 15 | 30 | | Cum | 1 | 15.00 | 0.50 | 0.50 | 0.50 | 0.50 | 3.75 | | |
| 30 | 45 | | Cum | 1 | 15.00 | 0.50 | 0.50 | 0.50 | 0.50 | 3.75 | | |
| 45 | 60 | | Cum | 1 | 15.00 | 0.50 | 0.50 | 0.50 | 0.50 | 3.75 | | |
| 60 | 75 | | Cum | 1 | 15.00 | 0.50 | 0.50 | 0.50 | 0.50 | 3.75 | | |
| 75 | 90 | | Cum | 1 | 15.00 | 0.50 | 0.50 | 0.50 | 0.50 | 3.75 | | |
| 90 | 105 | | Cum | 1 | 15.00 | 0.50 | 0.50 | 0.50 | 0.50 | 3.75 | | |
| 105 | 107.1 | | Cum | 1 | 2.10 | 0.50 | 0.50 | 0.50 | 0.50 | 0.52 | | |
| | | | | | | | | | | | | |
| | | North Side | | | | | | | | | | |
| 0 | 5.4 | | Cum | 1 | 5.40 | 0.50 | 0.50 | 0.50 | 0.50 | 1.35 | | |
| | | | | | | | | | | | | |
| | | South Side | | | | | | | | | | |
| 0 | 5.5 | | Cum | 1 | 5.50 | 0.50 | 0.50 | 0.50 | 0.50 | 1.38 | | |
| | | | | | | | | | | | | |
| | | East Side | | | | | | | | | | |
| 0 | 2.5 | Gate | Cum | 1 | 0.00 | 0.50 | 0.50 | 0.50 | 0.50 | 0.00 | | |
| 2.5 | 17.5 | | Cum | 1 | 15.00 | 0.50 | 0.50 | 0.50 | 0.50 | 3.75 | | |
| 17.5 | 32.5 | | Cum | 1 | 15.00 | 0.50 | 0.50 | 0.50 | 0.50 | 3.75 | | |
| 32.5 | 47.5 | | Cum | 1 | 15.00 | 0.50 | 0.50 | 0.50 | 0.50 | 3.75 | | |
| 47.5 | 62.5 | | Cum | 1 | 15.00 | 0.50 | 0.50 | 0.50 | 0.50 | 3.75 | | |
| 62.5 | 77.5 | | Cum | 1 | 15.00 | 0.50 | 0.50 | 0.50 | 0.50 | 3.75 | | |
| 77.5 | 92.5 | | Cum | 1 | 15.00 | 0.50 | 0.50 | 0.50 | 0.50 | 3.75 | | |
| 92.5 | 103.5 | | Cum | 1 | 11.00 | 0.50 | 0.50 | 0.50 | 0.50 | 2.75 | | |
| 103.5 | 105.7 | Gate | Cum | 1 | 0.00 | 0.50 | 0.50 | 0.50 | 0.50 | 0.00 | | |
| | | | | | | | | | | | | |
| | | Judicial Layout | | | | | | | | | | |
| | | South Side | | | | | | | | | | |
| 0 | 6.5 | | Cum | 1 | 6.50 | 0.60 | 0.60 | 0.60 | 0.90 | 3.51 | | |
| | | | | | | | | | | | | |
| | | West Side | | | | | | | | | | |
| 0 | 15 | | Cum | 1 | 15.00 | 0.60 | 0.60 | 0.60 | 0.90 | 8.10 | | |
| 15 | 25.65 | | Cum | 1 | 10.65 | 0.60 | 0.60 | 0.60 | 0.90 | 5.75 | | |
| | | | | | | | | | | | | |
| | | Deduction | | | | | | | | | | |
| | | Gate | Cum | 0 | 1.80 | 0.50 | 0.50 | 0.50 | 0.50 | 0.00 | | |
| | | | | | | | | | | | | |
| | | For Grill Pole Concrete | | | | | | | | | | |
| | | Parking Lot | | | | | | | | | | |
| | | Grill Between Car Parking And Bike Parking Near Temple | | | | | | | | | | |
| | | | Cum | -2 | 0.45 | 0.60 | 0.60 | 0.60 | 0.45 | -0.24 | | |
| | | Grill Between Car Parking And Bike Parking near Toilet | | | | | | | | | | |
| | | | Cum | -3 | 0.45 | 0.60 | 0.60 | 0.60 | 0.45 | -0.36 | | |
| | | | | | | | | | | | | |
| | | Temple Surrounding | | | | | | | | | | |
| | | North Side | Cum | -13 | 0.50 | 0.60 | 0.60 | 0.60 | 0.45 | -1.76 | | |
| | | East Side | Cum | -2 | 0.50 | 0.60 | 0.60 | 0.60 | 0.45 | -0.27 | | |
| | | South Side | Cum | -5 | 0.50 | 0.60 | 0.60 | 0.60 | 0.45 | -0.68 | | |
| | | | | | | | | | | | | |
| | | Parking Lot Near Public Toilet | | | | | | | | | | |
| | | South Side | | | | | | | | | | |
| | | | Cum | -8 | 0.45 | 0.60 | 0.60 | 0.60 | 0.50 | -1.08 | | |

| Chainage | | Description of Item | Unit | No | Length | Breadth | | | Depth | Qty | Rate | Amount |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| From | To | | | | | B1 | B2 | Avg | | | | |
| | | West Side | | | | | | | | | | |
| | | Arch Portion | Cum | -4 | 0.45 | 0.60 | 0.60 | 0.60 | 0.50 | -0.54 | | |
| | | North Side | Cum | -5 | 0.45 | 0.60 | 0.60 | 0.60 | 0.50 | -0.68 | | |
| | | 16th 'B' Cross Road Near Bus Stand | | | | | | | | | | |
| | | South Side | Cum | -4 | 0.45 | 0.60 | 0.60 | 0.60 | 0.45 | -0.49 | | |
| | | West Side | Cum | -12 | 0.45 | 0.60 | 0.60 | 0.60 | 0.45 | -1.46 | | |
| | | East Side | Cum | 0 | 0.45 | 0.60 | 0.60 | 0.60 | 0.45 | 0.00 | | |
| | | 16th B Cross Road | | | | | | | | | | |
| | | South Side | Cum | -34 | 0.45 | 0.60 | 0.60 | 0.60 | 0.45 | -4.13 | | |
| | | North Side | Cum | -33 | 0.45 | 0.60 | 0.60 | 0.60 | 0.45 | -4.01 | | |
| | | East Side | Cum | -3 | 0.45 | 0.60 | 0.60 | 0.60 | 0.45 | -0.36 | | |
| | | West Side | Cum | -3 | 0.45 | 0.60 | 0.60 | 0.60 | 0.45 | -0.36 | | |
| | | Judicial Layout | | | | | | | | | | |
| | | South Side | | | | | | | | | | |
| | | | Cum | -2 | 0.60 | 0.60 | 0.60 | 0.60 | 0.45 | -0.32 | | |
| | | West Side | | | | | | | | | | |
| | | | Cum | -9 | 0.60 | 0.60 | 0.60 | 0.60 | 0.45 | -1.46 | | |
| | | | | | | | | | **Total** | **93.09** | | |
| | | | | | | | | | **Tender Quantity** | **38.39** | | |
| | | | | | | | | | **Quantity Upto 125%** | **47.98** | **6674.02** | **320247.00** |
| | | | | | | | | | **Quantity Above 125%** | **45.11** | **6677.20** | **301182.00** |
| 7 | | Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregtes @ 0.43cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. and as per the directions of the Engineer-in-charge of the work | | | | | | | | | | |
| | | **For Grill Pole Concrete** | | | | | | | | | | |
| | | **Parking Lot** | | | | | | | | | | |
| | | **Grill Between Car Parking And Bike Parking Near Temple** | | | | | | | | | | |
| | | | Cum | 2 | 0.45 | 0.60 | 0.60 | 0.60 | 0.60 | 0.32 | | |
| | | Grill Between Car Parking And Bike Parking near Toilet | | | | | | | | | | |
| | | | Cum | 3 | 0.45 | 0.60 | 0.60 | 0.60 | 0.60 | 0.49 | | |
| | | Temple Surrounding | | | | | | | | | | |
| | | North Side | Cum | 13 | 0.50 | 0.60 | 0.60 | 0.60 | 0.60 | 2.34 | | |
| | | East Side | Cum | 2 | 0.50 | 0.60 | 0.60 | 0.60 | 0.60 | 0.36 | | |
| | | South Side | Cum | 5 | 0.50 | 0.60 | 0.60 | 0.60 | 0.60 | 0.90 | | |
| | | Parking Lot Near Public Toilet | | | | | | | | | | |
| | | South Side | | | | | | | | | | |
| | | | Cum | 8 | 0.45 | 0.60 | 0.60 | 0.60 | 0.60 | 1.30 | | |
| | | West Side | | | | | | | | | | |
| | | Arch Portion | Cum | 4 | 0.45 | 0.60 | 0.60 | 0.60 | 0.60 | 0.65 | | |
| | | North Side | Cum | 5 | 0.45 | 0.60 | 0.60 | 0.60 | 0.60 | 0.81 | | |
| | | 16th B Cross Road | | | | | | | | | | |
| | | South Side | Cum | 34 | 0.45 | 0.60 | 0.60 | 0.60 | 0.60 | 5.51 | | |
| | | North Side | Cum | 33 | 0.45 | 0.60 | 0.60 | 0.60 | 0.60 | 5.35 | | |
| | | East Side | Cum | 3 | 0.45 | 0.60 | 0.60 | 0.60 | 0.60 | 0.49 | | |
| | | West Side | Cum | 3 | 0.45 | 0.60 | 0.60 | 0.60 | 0.60 | 0.49 | | |

| Chainage | | Description of Item | Unit | No | Length | Breadth | | | Depth | Qty | Rate | Amount |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| From | To | | | | | B1 | B2 | Avg | | | | |
| | | | | | | | | | | | | |
| | | 16th 'B' Cross Road Near Bus Stand | | | | | | | | | | |
| | | South Side | Cum | 4 | 0.45 | 0.60 | 0.60 | 0.60 | 0.60 | 0.65 | | |
| | | West Side | Cum | 12 | 0.45 | 0.60 | 0.60 | 0.60 | 0.60 | 1.94 | | |
| | | East Side | Cum | 0 | 0.45 | 0.60 | 0.60 | 0.60 | 0.60 | 0.00 | | |
| | | Judicial Layout | | | | | | | | | | |
| | | South Side | | | | | | | | | | |
| | | | Cum | 2 | 0.60 | 0.60 | 0.60 | 0.60 | 0.60 | 0.43 | | |
| | | West Side | | | | | | | | | | |
| | | | Cum | 9 | 0.60 | 0.60 | 0.60 | 0.60 | 0.60 | 1.94 | | |
| | | Copping Concrete | | | | | | | | | | |
| | | parking Lot | | | | | | | | | | |
| | | Temple Surrounding | | | | | | | | | | |
| | | East Side | | | | | | | | | | |
| 0 | 5.55 | | Cum | 1 | 5.55 | 0.45 | 0.45 | 0.45 | 0.10 | 0.25 | | |
| 5.55 | 11.35 | No Work | Cum | 1 | 0.00 | 0.00 | 0.00 | 0.00 | 0.10 | 0.00 | | |
| | | South Side | | | | | | | | | | |
| 0 | 15 | | Cum | 1 | 15.00 | 0.45 | 0.47 | 0.46 | 0.10 | 0.69 | | |
| 15 | 18 | | Cum | 1 | 3.00 | 0.47 | 0.45 | 0.46 | 0.10 | 0.14 | | |
| 18 | 19.2 | Gate | Cum | 1 | 0.00 | 0.00 | 0.00 | 0.00 | 0.10 | 0.00 | | |
| 19.2 | 31.6 | | Cum | 1 | 12.40 | 0.47 | 0.50 | 0.49 | 0.10 | 0.60 | | |
| 31.6 | 33 | Gate | Cum | 1 | 0.00 | 0.00 | 0.00 | 0.00 | 0.10 | 0.00 | | |
| 33 | 35.2 | | Cum | 1 | 2.20 | 0.50 | 0.51 | 0.51 | 0.10 | 0.11 | | |
| | | North Side | | | | | | | | | | |
| 0 | 7.9 | No Work | Cum | 1 | 0.00 | 0.00 | 0.00 | 0.00 | 0.10 | 0.00 | | |
| 7.9 | 21.2 | | Cum | 1 | 13.30 | 0.45 | 0.45 | 0.45 | 0.10 | 0.60 | | |
| 21.2 | 35 | No Work | Cum | 1 | 0.00 | 0.00 | 0.00 | 0.00 | 0.10 | 0.00 | | |
| | | Between Car Parking And Bike Parking Lot Near Temple Side | | | | | | | | | | |
| 0 | 9.03 | | Cum | 1 | 9.03 | 0.45 | 0.45 | 0.45 | 0.10 | 0.41 | | |
| | | Between Car Parking And Bike Parking Lot Near Toilet | | | | | | | | | | |
| 0 | 9.3 | | Cum | 1 | 9.30 | 0.45 | 0.45 | 0.45 | 0.10 | 0.42 | | |
| | | Parking Lot Near Public Toilet | | | | | | | | | | |
| | | South Side | | | | | | | | | | |
| 0 | 1.9 | | Cum | 1 | 1.90 | 0.50 | 0.50 | 0.50 | 0.10 | 0.10 | | |
| 1.9 | 3.7 | Gate | Cum | 1 | 0.00 | 0.50 | 0.50 | 0.50 | 0.10 | 0.00 | | |
| 3.7 | 22.9 | | Cum | 1 | 19.20 | 0.50 | 0.50 | 0.50 | 0.10 | 0.96 | | |
| | | West Side | | | | | | | | | | |
| 0 | 14.05 | Arch Portion | Cum | 1 | 14.05 | 0.50 | 0.50 | 0.50 | 0.10 | 0.70 | | |
| | | North Side | | | | | | | | | | |
| 0 | 12.15 | | Cum | 1 | 12.15 | 0.50 | 0.50 | 0.50 | 0.10 | 0.61 | | |
| | | 16th B Cross Road | | | | | | | | | | |
| | | Service Road West Side | | | | | | | | | | |
| 0 | 15 | | Cum | 1 | 15.00 | 0.50 | 0.50 | 0.50 | 0.10 | 0.75 | | |
| 15 | 30 | | Cum | 1 | 15.00 | 0.50 | 0.50 | 0.50 | 0.10 | 0.75 | | |

| Chainage | | Description of Item | Unit | No | Length | Breadth | | | Depth | Qty | Rate | Amount |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| From | To | | | | | B1 | B2 | Avg | | | | |
| 30 | 45 | | | | | | | | | | | |
| 45 | 60 | | Cum | 1 | 15.00 | 0.50 | 0.50 | 0.50 | 0.10 | 0.75 | | |
| 60 | 75 | | Cum | 1 | 15.00 | 0.50 | 0.50 | 0.50 | 0.10 | 0.75 | | |
| 75 | 90 | | Cum | 1 | 15.00 | 0.50 | 0.50 | 0.50 | 0.10 | 0.75 | | |
| 90 | 105 | | Cum | 1 | 15.00 | 0.50 | 0.50 | 0.50 | 0.10 | 0.75 | | |
| 105 | 107.1 | | Cum | 1 | 15.00 | 0.50 | 0.50 | 0.50 | 0.10 | 0.75 | | |
| | | | Cum | 1 | 2.10 | 0.50 | 0.50 | 0.50 | 0.10 | 0.11 | | |
| | | North Side | | | | | | | | | | |
| 0 | 5.4 | | Cum | 1 | 5.40 | 0.50 | 0.50 | 0.50 | 0.10 | 0.27 | | |
| | | South Side | | | | | | | | | | |
| 0 | 5.5 | | Cum | 1 | 5.50 | 0.50 | 0.50 | 0.50 | 0.10 | 0.28 | | |
| | | East Side | | | | | | | | | | |
| 0 | 2.5 | Gate | Cum | 1 | 0.00 | 0.50 | 0.50 | 0.50 | 0.10 | 0.00 | | |
| 2.5 | 17.5 | | Cum | 1 | 15.00 | 0.50 | 0.50 | 0.50 | 0.10 | 0.75 | | |
| 17.5 | 32.5 | | Cum | 1 | 15.00 | 0.50 | 0.50 | 0.50 | 0.10 | 0.75 | | |
| 32.5 | 47.5 | | Cum | 1 | 15.00 | 0.50 | 0.50 | 0.50 | 0.10 | 0.75 | | |
| 47.5 | 62.5 | | Cum | 1 | 15.00 | 0.50 | 0.50 | 0.50 | 0.10 | 0.75 | | |
| 62.5 | 77.5 | | Cum | 1 | 15.00 | 0.50 | 0.50 | 0.50 | 0.10 | 0.75 | | |
| 77.5 | 92.5 | | Cum | 1 | 15.00 | 0.50 | 0.50 | 0.50 | 0.10 | 0.75 | | |
| 92.5 | 103.5 | | Cum | 1 | 11.00 | 0.50 | 0.50 | 0.50 | 0.10 | 0.55 | | |
| 103.5 | 105.7 | Gate | Cum | 1 | 0.00 | 0.50 | 0.50 | 0.50 | 0.10 | 0.00 | | |
| | | 16th 'B' Cross Road Near Bus Stand | | | | | | | | | | |
| | | South Side | | | | | | | | | | |
| 0 | 11.1 | | Cum | 1 | 11.10 | 0.50 | 0.50 | 0.50 | 0.10 | 0.56 | | |
| | | West Side | | | | | | | | | | |
| 0 | 15 | | Cum | 1 | 15.00 | 0.50 | 0.50 | 0.50 | 0.10 | 0.75 | | |
| 15 | 30 | | Cum | 1 | 15.00 | 0.50 | 0.50 | 0.50 | 0.10 | 0.75 | | |
| 30 | 37.6 | | Cum | 1 | 7.60 | 0.50 | 0.50 | 0.50 | 0.10 | 0.38 | | |
| | | Judicial Layout | | | | | | | | | | |
| | | South Side | | | | | | | | | | |
| 0 | 6.5 | | Cum | 1 | 6.50 | 0.60 | 0.60 | 0.60 | 0.10 | 0.39 | | |
| | | West Side | | | | | | | | | | |
| 0 | 15 | | Cum | 1 | 15.00 | 0.60 | 0.60 | 0.60 | 0.10 | 0.90 | | |
| 15 | 25.65 | | Cum | 1 | 10.65 | 0.60 | 0.60 | 0.60 | 0.10 | 0.64 | | |
| | | For Kerb PCC | | | | | | | | | | |
| | | Parking Lot | | | | | | | | | | |
| 0 | 15 | | Cum | 1 | 15.00 | 0.20 | 0.20 | 0.20 | 0.10 | 0.30 | | |
| 15 | 19.8 | | Cum | 1 | 4.80 | 0.20 | 0.20 | 0.20 | 0.10 | 0.10 | | |
| 19.8 | 21.3 | No Work | Cum | 1 | 0.00 | 0.20 | 0.20 | 0.20 | 0.10 | 0.00 | | |
| 21.3 | 36.3 | | Cum | 1 | 15.00 | 0.20 | 0.20 | 0.20 | 0.10 | 0.30 | | |
| 36.3 | 38.9 | | Cum | 1 | 2.60 | 0.20 | 0.20 | 0.20 | 0.10 | 0.05 | | |
| 38.9 | 56.3 | No Work | Cum | 1 | 0.00 | 0.20 | 0.20 | 0.20 | 0.10 | 0.00 | | |
| 56.3 | 71.3 | | Cum | 1 | 15.00 | 0.20 | 0.20 | 0.20 | 0.10 | 0.30 | | |
| 71.3 | 85.3 | | Cum | 1 | 14.00 | 0.20 | 0.20 | 0.20 | 0.10 | 0.28 | | |
| 85.3 | 86.6 | No Work | Cum | 1 | 0.00 | 0.20 | 0.20 | 0.20 | 0.10 | 0.00 | | |
| 86.6 | 101.6 | | Cum | 1 | 15.00 | 0.20 | 0.20 | 0.20 | 0.10 | 0.30 | | |
| 101.6 | 117.8 | | Cum | 1 | 16.20 | 0.20 | 0.20 | 0.20 | 0.10 | 0.32 | | |
| 117.8 | 118.6 | No Work | Cum | 1 | 0.00 | 0.20 | 0.20 | 0.20 | 0.10 | 0.00 | | |
| 118.6 | 133.6 | | Cum | 1 | 15.00 | 0.20 | 0.20 | 0.20 | 0.10 | 0.30 | | |
| 133.6 | 148.6 | | Cum | 1 | 15.00 | 0.20 | 0.20 | 0.20 | 0.10 | 0.30 | | |
| 148.6 | 157.6 | | Cum | 1 | 9.00 | 0.20 | 0.20 | 0.20 | 0.10 | 0.18 | | |
| 157.6 | 178.6 | No Work | Cum | 1 | 0.00 | 0.20 | 0.20 | 0.20 | 0.10 | 0.00 | | |
| 178.6 | 193.6 | | Cum | 1 | 15.00 | 0.20 | 0.20 | 0.20 | 0.10 | 0.30 | | |
| 193.6 | 203.8 | | Cum | 1 | 10.20 | 0.20 | 0.20 | 0.20 | 0.10 | 0.20 | | |

| Chainage | | Description of Item | Unit | No | Length | Breadth | | | Depth | Qty | Rate | Amount |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| From | To | | | | | B1 | B2 | Avg | | | | |
| 203.8 | 206 | No Work | Cum | 1 | 0.00 | 0.20 | 0.20 | 0.20 | 0.10 | 0.00 | | |
| 206 | 221 | | Cum | 1 | 15.00 | 0.20 | 0.20 | 0.20 | 0.10 | 0.30 | | |
| 221 | 236 | | Cum | 1 | 15.00 | 0.20 | 0.20 | 0.20 | 0.10 | 0.30 | | |
| 236 | 252 | | Cum | 1 | 16.00 | 0.20 | 0.20 | 0.20 | 0.10 | 0.32 | | |
| 252 | 253 | No Work | Cum | 1 | 0.00 | 0.20 | 0.20 | 0.20 | 0.10 | 0.00 | | |
| 253 | 268 | | Cum | 1 | 15.00 | 0.20 | 0.20 | 0.20 | 0.10 | 0.30 | | |
| 268 | 273.2 | | Cum | 1 | 5.20 | 0.20 | 0.20 | 0.20 | 0.10 | 0.10 | | |
| 273.2 | 291.2 | No Work | Cum | 1 | 0.00 | 0.20 | 0.20 | 0.20 | 0.10 | 0.00 | | |
| 291.2 | 299.5 | | Cum | 1 | 8.30 | 0.20 | 0.20 | 0.20 | 0.10 | 0.17 | | |
| 299.5 | 301.7 | No Work | Cum | 1 | 0.00 | 0.20 | 0.20 | 0.20 | 0.10 | 0.00 | | |
| 301.7 | 304 | | Cum | 1 | 2.30 | 0.20 | 0.20 | 0.20 | 0.10 | 0.05 | | |
| | | 16th 'B' Cross Road | | | | | | | | | | |
| 0 | 15 | | Cum | 1 | 15.00 | 5.95 | 5.95 | 5.95 | 0.15 | 13.39 | | |
| 15 | 30 | | Cum | 1 | 15.00 | 5.95 | 5.95 | 5.95 | 0.15 | 13.39 | | |
| 30 | 37.6 | | Cum | 1 | 7.60 | 5.95 | 5.95 | 5.95 | 0.15 | 6.78 | | |
| | | Judicial Layout | | | | | | | | | | |
| 0 | 2.65 | | Cum | 1 | 2.65 | 6.40 | 6.40 | 6.40 | 0.15 | 2.54 | | |
| 2.65 | 17.65 | | Cum | 1 | 15.00 | 4.90 | 4.90 | 4.90 | 0.15 | 11.03 | | |
| 17.65 | 23.65 | | Cum | 1 | 6.00 | 4.90 | 4.90 | 4.90 | 0.15 | 4.41 | | |
| 23.65 | 25.45 | | Cum | 1 | 1.80 | 6.00 | 6.00 | 6.00 | 0.15 | 1.62 | | |
| | | Deduction | | | | | | | | | | |
| | | | Cum | -1 | 2.10 | 1.90 | 1.90 | 1.90 | 0.15 | -0.60 | | |
| | | Gate | Cum | 0 | 1.80 | 0.50 | 0.50 | 0.50 | 0.10 | 0.00 | | |
| | | Door | Sqm | -1 | 2.54 | 0.87 | 0.87 | 0.87 | 0.10 | -0.22 | | |
| | | Borewell | Sqm | -1 | 1.20 | 0.90 | 0.90 | 0.90 | 0.10 | -0.11 | | |
| | | Chamber | Sqm | -2 | 1.00 | 0.70 | 0.70 | 0.70 | 0.10 | -0.14 | | |
| | | | | | | | | | Total | 101.71 | 5921.59 | 602298.00 |
| | | | | | | | | | Tender Quantity | 110.85 | | |
| 8 | | Providing and laying M-15 cement concrete flooring 60 mm thick with metallic concrete hardner toping, under layer of 45mm thick M-15 cement concrete using broken granite metal of 20mm and down size and top layer of 15mm thick metallic cement hardner consisting of mix 1:2 ( 1 cement hardner mix : 2 granite metal 10mm nominal size ) by volume, with metalic hardening compound of approved quality mix in the ratio of 4:1 ( 4 part of cement = 1 part of metallic floor hardening compound of approved quality by wt ) , including finishing, cost of materials, labour, curing, complete as per specifications. and as per the directions of the Engineer-in-charge of the work | | | | | | | | | | |
| | | Parking Lot | | | | | | | | | | |
| | | temple portion | | | | | | | | | | |
| 0 | 1.17 | | Sqm | 1 | 1.17 | 10.86 | 10.86 | 10.86 | | 12.71 | | |
| 1.17 | 14 | | Sqm | 1 | 12.83 | 13.88 | 12.68 | 13.28 | | 170.38 | | |
| 14 | 16 | | Sqm | 1 | 2.00 | 12.68 | 10.86 | 11.77 | | 23.54 | | |
| 16 | 20.4 | | Sqm | 1 | 4.40 | 10.86 | 13.16 | 12.01 | | 52.84 | | |
| 20.4 | 24.7 | | Sqm | 1 | 4.30 | 13.16 | 14.29 | 13.73 | | 59.02 | | |
| | | 16th B Cross Road | | | | | | | | | | |
| 0 | 15 | | Sqm | 1 | 15.00 | 5.00 | 5.00 | 5.00 | | 75.00 | | |
| 15 | 30 | | Sqm | 1 | 15.00 | 5.00 | 5.00 | 5.00 | | 75.00 | | |
| 30 | 45 | | Sqm | 1 | 15.00 | 5.00 | 5.00 | 5.00 | | 75.00 | | |
| 45 | 60 | | Sqm | 1 | 15.00 | 5.00 | 5.00 | 5.00 | | 75.00 | | |
| 60 | 75 | | Sqm | 1 | 15.00 | 5.00 | 5.05 | 5.03 | | 75.38 | | |
| 75 | 90 | | Sqm | 1 | 15.00 | 5.00 | 5.00 | 5.00 | | 75.00 | | |
| 90 | 105 | | Sqm | 1 | 15.00 | 5.00 | 9.00 | 7.00 | | 105.00 | | |
| | | 16th 'B' Cross Road | | | | | | | | | | |
| 0 | 15 | | Sqm | 1 | 15.00 | 5.95 | 5.95 | 5.95 | | 89.25 | | |
| 15 | 30 | | Sqm | 1 | 15.00 | 5.95 | 5.95 | 5.95 | | 89.25 | | |
| 30 | 37.6 | | Sqm | 1 | 7.60 | 5.95 | 5.95 | 5.95 | | 45.22 | | |
| | | Judicial Layout | | | | | | | | | | |
| 0 | 2.65 | | Sqm | 1 | 2.65 | 6.40 | 6.40 | 6.40 | | 16.96 | | |

| Chainage | | Description of Item | Unit | No | Length | Breadth | | | Depth | Qty | Rate | Amount |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| From | To | | | | | B1 | B2 | Avg | | | | |
| 2.65 | 17.65 | | Sqm | 1 | 15.00 | 4.90 | 4.90 | 4.90 | | 73.50 | | |
| 17.65 | 23.65 | | Sqm | 1 | 6.00 | 4.90 | 4.90 | 4.90 | | 29.40 | | |
| 23.65 | 25.45 | | Sqm | 1 | 1.80 | 6.00 | 6.00 | 6.00 | | 10.80 | | |
| | | Deduction | | | | | | | | | | |
| | | | Sqm | -1 | 2.10 | 1.90 | 1.90 | 1.90 | | -3.99 | | |
| | | Temple Portion | | | | | | | | | | |
| | | Public Toilet | Sqm | -1 | 7.82 | 12.20 | 12.20 | 12.20 | | -95.40 | | |
| | | 0 | Sqm | -1 | 3.65 | 5.50 | 5.50 | 5.50 | | -20.08 | | |
| | | Sump | Sqm | -1 | 3.44 | 1.22 | 1.22 | 1.22 | | -4.20 | | |
| | | Tree | Sqm | -1 | 0.90 | 0.60 | 0.60 | 0.60 | | -0.54 | | |
| | | Temple | Sqm | -1 | 4.00 | 5.94 | 5.94 | 5.94 | | -23.76 | | |
| | | | Sqm | -1 | 2.50 | 3.15 | 3.15 | 3.15 | | -7.88 | | |
| | | Door | Sqm | -1 | 2.54 | 0.87 | 0.87 | 0.87 | | -2.21 | | |
| | | Borewell | Sqm | -1 | 1.20 | 0.90 | 0.90 | 0.90 | | -1.08 | | |
| | | Chamber | Sqm | -2 | 1.00 | 0.70 | 0.70 | 0.70 | | -1.40 | | |
| | | | | | | | | | Total | 1067.71 | | |
| | | | | | | | | | Tender Quantity | 807.36 | | |
| | | | | | | | | | Quantity Upto 125% | 1009.20 | 779.10 | 786268.00 |
| | | | | | | | | | Quantity Above 125% | 58.51 | 779.47 | 45611.00 |
| 9 | | Fabricating providing and erecting in position of MS Hot Dip galvanized sq hallow poles of 132 x132 heavy gauge length 3000mm with MS Hot Dip galvanized grill work as per approved design and drawing of chief architect using 12 x75mm galvanized flat for alround frame and 20 x 20mm galvanized forged ornamental arrow head in top and buttom the work is inclusive of throughing flat square rods placing welding all the joints including griding finishing 2 coats of anticorrossive paint over one coat of metal primer the rate is inclusive of all materials all items of work cost painting welding cutting griding with lead and lift as per specifications including loading and unloading with cost and conveyance of all materials labour machinery and incidental charges for the successful completion of the work as per direction of engineer in charge of work | | | | | | | | | | | |
| | | parking Lot | | | | | | | | | | |
| | | Temple Surrounding | | | | | | | | | | |
| | | East Side | | | | | | | | | | |
| 0 | 5.8 | | Sqm | 1 | 5.80 | | | | 1.90 | 11.02 | | |
| | | South Side | | | | | | | | | | |
| 0 | 15 | | Sqm | 1 | 15.00 | | | | 1.83 | 27.45 | | |
| 15 | 18.3 | | Sqm | 1 | 3.30 | | | | 1.80 | 5.94 | | |
| 18.3 | 20.1 | Gate | Sqm | 1 | 0.00 | | | | 1.83 | 0.00 | | |
| 20.1 | 32.3 | | Sqm | 1 | 12.20 | | | | 1.90 | 23.18 | | |
| 32.3 | 33.8 | Gate | Sqm | 1 | 0.00 | | | | 1.90 | 0.00 | | |
| 33.8 | 36.2 | | Sqm | 1 | 2.40 | | | | 1.90 | 4.56 | | |
| | | North Side | | | | | | | | | | |
| 0 | 8.1 | No Work | Sqm | 1 | 0.00 | | | | 0.00 | 0.00 | | |
| 8.1 | 21.1 | | Sqm | 1 | 13.00 | | | | 1.84 | 23.92 | | |
| 21.1 | 34.9 | No Work | Sqm | 0 | 0.00 | | | | 1.84 | 0.00 | | |
| | | Between Car Parking And Bike Parking Lot Near Temple Side | | | | | | | | | | |
| 0 | 9.05 | 2pole | Sqm | 1 | 9.05 | | | | 1.80 | 16.29 | | |
| | | Between Car Parking And Bike Parking Lot Near Toilet | | | | | | | | | | |
| 0 | 9.3 | | Sqm | 1 | 9.30 | | | | 1.98 | 18.41 | | |
| | | Parking Lot Near Public Toilet | | | | | | | | | | |
| | | South Side | | | | | | | | | | |
| 0 | 1.9 | | Sqm | 1 | 1.90 | | | | 1.75 | 3.33 | | |

| Chainage | | Description of Item | Unit | No | Length | Breadth | | | Depth | Qty | Rate | Amount |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| From | To | | | | | B1 | B2 | Avg | | | | |
| 1.9 | 3.7 | Gate | Sqm | 1 | 0.00 | | | | 0.00 | 0.00 | | |
| 3.7 | 22.9 | | Sqm | 1 | 19.20 | | | | 1.88 | 36.10 | | |
| | | West Side | | | | | | | | | | |
| 0 | 14.05 | Arch Portion | Sqm | 1 | 14.05 | | | | 1.88 | 26.41 | | |
| | | North Side | | | | | | | | | | |
| 0 | 12.15 | | Sqm | 1 | 12.15 | | | | 1.88 | 22.84 | | |
| | | 16th B Cross Road | | | | | | | | | | |
| | | Service Road West Side | | | | | | | | | | |
| 0 | 15 | | Sqm | 1 | 15.00 | | | | 1.50 | 22.50 | | |
| 15 | 30 | | Sqm | 1 | 15.00 | | | | 1.50 | 22.50 | | |
| 30 | 45 | | Sqm | 1 | 15.00 | | | | 1.50 | 22.50 | | |
| 45 | 60 | | Sqm | 1 | 15.00 | | | | 1.50 | 22.50 | | |
| 60 | 75 | | Sqm | 1 | 15.00 | | | | 1.50 | 22.50 | | |
| 75 | 90 | | Sqm | 1 | 15.00 | | | | 1.50 | 22.50 | | |
| 90 | 105 | | Sqm | 1 | 15.00 | | | | 1.50 | 22.50 | | |
| 105 | 107.1 | | Sqm | 1 | 2.10 | | | | 1.50 | 3.15 | | |
| | | North Side | | | | | | | | | | |
| 0 | 5.4 | | Sqm | 1 | 5.40 | | | | 1.50 | 8.10 | | |
| | | South Side | | | | | | | | | | |
| 0 | 5.5 | | Sqm | 1 | 5.50 | | | | 1.50 | 8.25 | | |
| | | East Side | | | | | | | | | | |
| 0 | 2.5 | Gate | Sqm | 1 | 0.00 | | | | 1.50 | 0.00 | | |
| 2.5 | 17.5 | | Sqm | 1 | 15.00 | | | | 1.50 | 22.50 | | |
| 17.5 | 32.5 | | Sqm | 1 | 15.00 | | | | 1.50 | 22.50 | | |
| 32.5 | 47.5 | | Sqm | 1 | 15.00 | | | | 1.50 | 22.50 | | |
| 47.5 | 62.5 | | Sqm | 1 | 15.00 | | | | 1.50 | 22.50 | | |
| 62.5 | 77.5 | | Sqm | 1 | 15.00 | | | | 1.50 | 22.50 | | |
| 77.5 | 92.5 | | Sqm | 1 | 15.00 | | | | 1.50 | 22.50 | | |
| 92.5 | 103.5 | | Sqm | 1 | 11.00 | | | | 1.50 | 16.50 | | |
| 103.5 | 105.7 | Gate | Sqm | 1 | 0.00 | | | | 1.50 | 0.00 | | |
| | | 16th 'B' Cross Road Near Bus Stand | | | | | | | | | | |
| | | South Side | | | | | | | | | | |
| 0 | 11.1 | | Sqm | 1 | 11.10 | | | | 1.50 | 16.65 | | |
| | | West Side | | | | | | | | | | |
| 0 | 15 | | Sqm | 1 | 15.00 | | | | 1.50 | 22.50 | | |
| 15 | 30 | | Sqm | 1 | 15.00 | | | | 1.50 | 22.50 | | |
| 30 | 37.6 | | Sqm | 1 | 7.60 | | | | 1.50 | 11.40 | | |
| | | Judicial Layout | | | | | | | | | | |
| | | West Side | | | | | | | | | | |
| 0 | 9.4 | | Sqm | 1 | 9.40 | | | | 1.50 | 14.10 | | |
| 9.4 | 13.05 | gate | Sqm | 1 | 0.00 | | | | 1.50 | 0.00 | | |
| 13.05 | 25.6 | | Sqm | 1 | 12.55 | | | | 1.50 | 18.83 | | |
| | | North Side | | | | | | | | | | |
| 0 | 6.2 | | Sqm | 1 | 6.20 | | | | 1.50 | 9.30 | | |
| | | South Side | | | | | | | | | | |
| 0 | 6.2 | | Sqm | 1 | 6.20 | | | | 1.50 | 9.30 | | |
| | | | | | | | | | Total | 672.53 | 9587.63 | 6447931.00 |
| | | | | | | | | | Tender Quantity | 807.93 | | |

| Chainage | | Description of Item | Unit | No | Length | Breadth | | | Depth | Qty | Rate | Amount |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| From | To | | | | | B1 | B2 | Avg | | | | |
| 10 | | Fabricating, providing and erecting in position Hot dip galvanized Gate. Using 72x72x4.8 mm Sq. G I Pipe Frame with top pipe bending in heavy duty hydraulic press with sand packing and hot bending to form double arch as per drawing profile, 20mm hot dip galvanized sq rod for verticals at 150mm c/c , as shown in the drawing including providing hot do galvanized forged ornamental design in between rods and heads at top, middle and bottom. Intermediate supports of 75x12mm and 50x6mm arch bent to hot dip galvanized flats.The work is inclusive of throughing GI, Flat GI Sqm. rods, placing, welding all the joints including grinding, finishing metal patty, painting two coats enamel painting. The rate is inclusive of all materials Like GI Sq. GI Pipe, GI Forged designs etc., heavy duty hinges are made out of 75mm sold sq. block assembled with 20mm du bearing in three places for each flop. Heavy duty locking arrangement of low places including cost of labour, painting, erection charges using hoist pulley cranes, with all lead and lift, loading, trasportation, unloading, scaffolding and as per the directions of the Engineer-in-charge of the work | | | | | | | | | | |
| | | Temple Back Side | Sqm | 1 | 1.50 | | | | 1.80 | 2.70 | | |
| | | R.O.Plant Oppo. | Sqm | 1 | 1.25 | | | | 1.80 | 2.25 | | |
| | | | | | | | | | | | | |
| | | Sliding Gates | | | | | | | | | | |
| | | Bike Parking | Sqm | 2 | 3.00 | | | | 1.97 | 11.82 | | |
| | | | | | | | | | | | | |
| | | Gates in Car parking(one entry and one exit) | Sqm | 2 | 5.00 | | | | 1.98 | 19.80 | | |
| | | | | | | | | | | | | |
| | | Public Toilet Front | Sqm | 1 | 1.80 | | | | 1.50 | 2.70 | | |
| | | | | | | | | | | | | |
| | | 16th B Cross Road | Sqm | 2 | 1.80 | | | | 1.80 | 6.48 | | |
| | | | | | | | | | | | | |
| | | Judicial Layout | Sqm | 1 | 3.65 | | | | 1.80 | 6.57 | | |
| | | | | | | | | | Total | 52.32 | 13080.07 | 684350.00 |
| | | | | | | | | | Tender Quantity | 58.56 | | |
| 11 | | Providing and constructing load bearing wall with solid concrete blocks of size 400x150x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 4.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing complete as per specifications. and as per the directions of the Engineer-in-charge of the work | | | | | | | | | | |
| | | **Parking Lot** | | | | | | | | | | |
| | | From Public Toilet To Bike parking | | | | | | | | | | |
| 0.00 | 15.00 | | Sqm | 1 | 15.00 | | | | 0.30 | 4.50 | | |
| 15.00 | 19.40 | | Sqm | 1 | 4.40 | | | | 0.40 | 1.76 | | |
| 19.40 | 21.20 | No Work | Sqm | 1 | 0.00 | | | | 0.00 | 0.00 | | |
| 21.20 | 30.00 | | Sqm | 1 | 8.80 | | | | 0.40 | 3.52 | | |
| 30.00 | 38.70 | | Sqm | 1 | 8.70 | | | | 0.40 | 3.48 | | |
| 38.70 | 56.00 | No Work | Sqm | 1 | 0.00 | | | | 0.00 | 0.00 | | |
| 56.00 | 60.00 | | Sqm | 1 | 4.00 | | | | 0.80 | 3.20 | | |
| 60.00 | 75.00 | | Sqm | 1 | 15.00 | | | | 0.80 | 12.00 | | |
| 75.00 | 84.70 | | Sqm | 1 | 9.70 | | | | 0.80 | 7.76 | | |
| 84.70 | 86.30 | No Work | Sqm | 1 | 0.00 | | | | 0.80 | 0.00 | | |
| 86.30 | 90.00 | | Sqm | 1 | 3.70 | | | | 0.80 | 2.96 | | |
| 90.00 | 105.00 | | Sqm | 1 | 15.00 | | | | 0.80 | 12.00 | | |
| 105.00 | 120.00 | | Sqm | 1 | 15.00 | | | | 0.80 | 12.00 | | |
| 120.00 | 135.00 | | Sqm | 1 | 15.00 | | | | 0.80 | 12.00 | | |
| 135.00 | 150.00 | | Sqm | 1 | 15.00 | | | | 0.80 | 12.00 | | |
| 150.00 | 156.30 | | Sqm | 1 | 6.30 | | | | 0.80 | 5.04 | | |
| 156.30 | 177.10 | No Work | Sqm | 1 | 0.00 | | | | 0.80 | 0.00 | | |
| 177.10 | 185.00 | | Sqm | 1 | 7.90 | | | | 0.80 | 6.32 | | |
| 185.00 | 195.00 | | Sqm | 1 | 10.00 | | | | 0.80 | 8.00 | | |
| 195.00 | 210.00 | | Sqm | 1 | 15.00 | | | | 0.80 | 12.00 | | |
| 210.00 | 225.00 | | Sqm | 1 | 15.00 | | | | 0.80 | 12.00 | | |
| 225.00 | 240.00 | | Sqm | 1 | 15.00 | | | | 0.80 | 12.00 | | |
| 240.00 | 255.00 | | Sqm | 1 | 15.00 | | | | 0.80 | 12.00 | | |
| 255.00 | 261.30 | No Work | Sqm | 1 | 0.00 | | | | 0.80 | 0.00 | | |
| 261.30 | 271.50 | | Sqm | 1 | 10.20 | | | | 0.80 | 8.16 | | |
| 271.50 | 289.30 | No Work | Sqm | 1 | 0.00 | | | | 0.80 | 0.00 | | |
| 289.30 | 302.20 | | Sqm | 1 | 12.90 | | | | 0.80 | 10.32 | | |
| | | | | | | | | | | | | |
| | | Deduction | | | | | | | | | | |

| Chainage From | Chainage To | Description of Item | Unit | No | Length | Breadth B1 | Breadth B2 | Breadth Avg | Depth | Qty | Rate | Amount |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | Arch Portions | | | | | | | | | | |
| | | | Sqm | -1 | 1.20 | | | | 0.80 | -0.96 | | |
| | | | Sqm | -1 | 1.20 | | | | 0.80 | -0.96 | | |
| | | | Sqm | -1 | 1.20 | | | | 0.80 | -0.96 | | |
| | | | Sqm | -1 | 1.20 | | | | 0.80 | -0.96 | | |
| | | | Sqm | -1 | 1.20 | | | | 0.80 | -0.96 | | |
| | | | Sqm | -1 | 1.20 | | | | 0.80 | -0.96 | | |
| | | | Sqm | -1 | 1.20 | | | | 0.80 | -0.96 | | |
| | | | Sqm | -1 | 1.20 | | | | 0.80 | -0.96 | | |
| | | | Sqm | -1 | 1.20 | | | | 0.80 | -0.96 | | |
| | | | Sqm | -1 | 1.20 | | | | 0.80 | -0.96 | | |
| | | | Sqm | -1 | 1.20 | | | | 0.80 | -0.96 | | |
| | | | Sqm | -1 | 1.20 | | | | 0.80 | -0.96 | | |
| | | | Sqm | -1 | 1.20 | | | | 0.80 | -0.96 | | |
| | | | Sqm | -1 | 1.20 | | | | 0.80 | -0.96 | | |
| | | | Sqm | -1 | 1.20 | | | | 0.80 | -0.96 | | |
| | | | Sqm | -1 | 1.20 | | | | 0.80 | -0.96 | | |
| | | | Sqm | -1 | 1.20 | | | | 0.80 | -0.96 | | |
| | | | Sqm | -1 | 1.20 | | | | 0.80 | -0.96 | | |
| | | | Sqm | -1 | 1.20 | | | | 0.80 | -0.96 | | |
| | | | Sqm | -1 | 1.20 | | | | 0.80 | -0.96 | | |
| | | | Sqm | -1 | 1.20 | | | | 0.80 | -0.96 | | |
| | | | Sqm | -1 | 1.20 | | | | 0.80 | -0.96 | | |
| | | | Sqm | -1 | 1.20 | | | | 0.80 | -0.96 | | |
| | | | | | | | | | Total | 152.86 | 1026.94 | 156979.00 |
| | | | | | | | | | Tender Quantity | 219.92 | | |
| 12 | | Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners, wherever required smooth rendering, Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per the directions of the Engineer-in-charge of the work | | | | | | | | | | |
| | | Between Car Parking And Bike parking | | | | | | | | | | |
| 0 | 9.03 | Top | Sqm | 1 | 9.03 | 0.50 | 0.50 | 0.50 | | 4.52 | | |
| 0 | 9.03 | Wall | Sqm | 2 | 9.03 | | | | 0.45 | 8.13 | | |
| | | | | | | | | | | | | |
| | | Bike Parking Near Temple Beside Service Road | | | | | | | | | | |
| 0 | 15 | Wall | Sqm | 1 | 15.00 | | | | 0.30 | 4.50 | | |
| 15 | 17.3 | Wall | Sqm | 1 | 2.30 | | | | 0.30 | 0.69 | | |
| | | | | | | | | | | | | |
| | | East Side | | | | | | | | | | |
| 0 | 8.7 | Wall | Sqm | 1 | 8.70 | | | | 0.15 | 1.31 | | |
| 0 | 8.7 | Top | Sqm | 1 | 8.70 | 0.45 | 0.45 | 0.45 | | 3.92 | | |
| | | | | | | | | | | | | |
| | | Car Parking Service Road Side | | | | | | | | | | |
| 0 | 15 | | Sqm | 1 | 15.00 | | | | 0.35 | 5.25 | | |
| 15 | 30 | | Sqm | 1 | 15.00 | | | | 0.30 | 4.50 | | |
| 30 | 45 | | Sqm | 1 | 15.00 | | | | 0.30 | 4.50 | | |
| 45 | 60 | | Sqm | 1 | 15.00 | | | | 0.30 | 4.50 | | |
| 60 | 75 | | Sqm | 1 | 15.00 | | | | 0.30 | 4.50 | | |
| 75 | 90 | | Sqm | 1 | 15.00 | | | | 0.30 | 4.50 | | |
| 90 | 105 | | Sqm | 1 | 15.00 | | | | 0.30 | 4.50 | | |
| 105 | 106.6 | | Sqm | 1 | 1.60 | | | | 0.30 | 0.48 | | |
| 106.6 | 115.2 | Gate | Sqm | 1 | 0.00 | | | | 0.30 | 0.00 | | |
| 115.2 | 120 | | Sqm | 1 | 4.80 | | | | 0.30 | 1.44 | | |
| 120 | 135 | | Sqm | 1 | 15.00 | | | | 0.30 | 4.50 | | |
| 135 | 150 | | Sqm | 1 | 15.00 | | | | 0.30 | 4.50 | | |
| 150 | 165 | | Sqm | 1 | 15.00 | | | | 0.30 | 4.50 | | |
| 165 | 180 | | Sqm | 1 | 15.00 | | | | 0.30 | 4.50 | | |
| 180 | 195 | | Sqm | 1 | 15.00 | | | | 0.30 | 4.50 | | |
| 195 | 210 | | Sqm | 1 | 15.00 | | | | 0.30 | 4.50 | | |
| 210 | 225 | | Sqm | 1 | 15.00 | | | | 0.30 | 4.50 | | |
| 225 | 228.7 | | Sqm | 1 | 3.70 | | | | 0.30 | 1.11 | | |

| Chainage | | Description of Item | Unit | No | Length | Breadth | | | Depth | Qty | Rate | Amount |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| From | To | | | | | B1 | B2 | Avg | | | | |
| | | Between Car Parking and Bike parking | | | | | | | | | | |
| | | Service Road Side | | | | | | | | | | |
| 0 | 9.3 | Top | Sqm | 1 | 9.30 | 0.50 | 0.50 | 0.50 | | 4.65 | | |
| 0 | 9.3 | Wall | Sqm | 2 | 9.30 | | | | 0.16 | 2.98 | | |
| | | Bike Parking Near Toilet Beside Service Road | | | | | | | | | | |
| 0 | 15 | | Sqm | 1 | 15.00 | | | | 0.22 | 3.30 | | |
| 15 | 17.8 | | Sqm | 1 | 2.80 | | | | 0.17 | 0.48 | | |
| | | Doddaballapura Main Road Side | | | | | | | | | | |
| | | RHS | | | | | | | | | | |
| 0 | 15 | | Sqm | 1 | 15.00 | 0.90 | 1.07 | 0.99 | | 14.78 | | |
| 15 | 30 | | Sqm | 1 | 15.00 | 1.07 | 1.12 | 1.10 | | 16.43 | | |
| 30 | 45 | | Sqm | 1 | 15.00 | 1.12 | 1.20 | 1.16 | | 17.40 | | |
| 45 | 60 | | Sqm | 1 | 15.00 | 1.20 | 1.25 | 1.23 | | 18.38 | | |
| 60 | 75 | | Sqm | 1 | 15.00 | 1.25 | 1.00 | 1.13 | | 16.88 | | |
| 75 | 90 | | Sqm | 1 | 15.00 | 1.00 | 1.20 | 1.10 | | 16.50 | | |
| 90 | 105 | | Sqm | 1 | 15.00 | 1.20 | 1.20 | 1.20 | | 18.00 | | |
| 105 | 120 | | Sqm | 1 | 15.00 | 1.20 | 1.10 | 1.15 | | 17.25 | | |
| 120 | 135 | | Sqm | 1 | 15.00 | 1.10 | 1.22 | 1.16 | | 17.40 | | |
| 135 | 150 | | Sqm | 1 | 15.00 | 1.22 | 1.28 | 1.25 | | 18.75 | | |
| 150 | 165 | | Sqm | 1 | 15.00 | 1.28 | 1.15 | 1.22 | | 18.23 | | |
| 165 | 180 | | Sqm | 1 | 15.00 | 1.15 | 1.15 | 1.15 | | 17.25 | | |
| 180 | 195 | | Sqm | 1 | 15.00 | 1.15 | 1.14 | 1.15 | | 17.18 | | |
| 195 | 210 | | Sqm | 1 | 15.00 | 1.14 | 1.17 | 1.16 | | 17.33 | | |
| 210 | 225 | | Sqm | 1 | 15.00 | 1.17 | 1.15 | 1.16 | | 17.40 | | |
| 225 | 240 | | Sqm | 1 | 15.00 | 1.15 | 1.15 | 1.15 | | 17.25 | | |
| 240 | 255 | | Sqm | 1 | 15.00 | 1.15 | 1.25 | 1.20 | | 18.00 | | |
| 255 | 270 | | Sqm | 1 | 15.00 | 1.25 | 1.18 | 1.22 | | 18.23 | | |
| 270 | 275.7 | | Sqm | 1 | 5.70 | 1.18 | 1.18 | 1.18 | | 6.73 | | |
| | | Parking Lot Near Public Toilet | | | | | | | | | | |
| | | West Side | | | | | | | | | | |
| | | Arch Portion | Sqm | 1 | 14.05 | 0.50 | 0.50 | 0.50 | | 7.03 | | |
| | | wall | Sqm | 2 | 14.05 | | | | 0.30 | 8.43 | | |
| | | North Side | | | | | | | | | | |
| | | | Sqm | 1 | 12.15 | 0.50 | 0.50 | 0.50 | | 6.08 | | |
| | | Wall | | | | | | | | | | |
| | | | Sqm | 2 | 12.15 | | | | 0.30 | 7.29 | | |
| | | Temple Surrounding | | | | | | | | | | |
| | | Top | | | | | | | | | | |
| | | East Side | | | | | | | | | | |
| 0 | 5.55 | | Cum | 1 | 5.55 | 0.45 | 0.45 | 0.45 | | 2.50 | | |
| 5.55 | 11.35 | No Work | Cum | 1 | 0.00 | 0.00 | 0.00 | 0.00 | | 0.00 | | |
| | | South Side | | | | | | | | | | |
| 0 | 15 | | Cum | 1 | 15.00 | 0.45 | 0.47 | 0.46 | | 6.90 | | |
| 15 | 18 | | Cum | 1 | 3.00 | 0.47 | 0.45 | 0.46 | | 1.38 | | |
| 18 | 19.2 | Gate | Cum | 1 | 0.00 | 0.00 | 0.00 | 0.00 | | 0.00 | | |
| 19.2 | 31.6 | | Cum | 1 | 12.40 | 0.47 | 0.50 | 0.49 | | 6.01 | | |
| 31.6 | 33 | Gate | Cum | 1 | 0.00 | 0.00 | 0.00 | 0.00 | | 0.00 | | |
| 33 | 35.2 | | Cum | 1 | 2.20 | 0.50 | 0.51 | 0.51 | | 1.11 | | |
| | | North Side | | | | | | | | | | |

| Chainage | | Description of Item | Unit | No | Length | Breadth | | | Depth | Qty | Rate | Amount |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| From | To | | | | | B1 | B2 | Avg | | | | |
| 0 | 7.9 | No Work | Cum | 1 | 0.00 | 0.00 | 0.00 | 0.00 | | 0.00 | | |
| 7.9 | 21.2 | | Cum | 1 | 13.30 | 0.45 | 0.45 | 0.45 | | 5.99 | | |
| 21.2 | 35 | No Work | Cum | 1 | 0.00 | 0.00 | 0.00 | 0.00 | | 0.00 | | |
| | | | | | | | | | | | | |
| | | Wall | | | | | | | | | | |
| | | Temple Surrounding | | | | | | | | | | |
| | | Top | | | | | | | | | | |
| | | East Side | | | | | | | | | | |
| 0 | 5.55 | | Cum | 1 | 5.55 | | | | 0.40 | 2.22 | | |
| 5.55 | 11.35 | No Work | Cum | 1 | 0.00 | | | | 0.00 | 0.00 | | |
| | | | | | | | | | | | | |
| | | South Side | | | | | | | | | | |
| 0 | 15 | | Cum | 1 | 15.00 | | | | 0.45 | 6.75 | | |
| 15 | 18 | | Cum | 1 | 3.00 | | | | 0.45 | 1.35 | | |
| 18 | 19.2 | Gate | Cum | 1 | 0.00 | | | | 0.00 | 0.00 | | |
| 19.2 | 31.6 | | Cum | 1 | 12.40 | | | | 0.41 | 5.02 | | |
| 31.6 | 33 | Gate | Cum | 1 | 0.00 | | | | 0.00 | 0.00 | | |
| 33 | 35.2 | | Cum | 1 | 2.20 | | | | 0.41 | 0.90 | | |
| | | | | | | | | | | | | |
| | | North Side | | | | | | | | | | |
| 0 | 7.9 | No Work | Cum | 1 | 0.00 | | | | 0.00 | 0.00 | | |
| 7.9 | 21.2 | | Cum | 1 | 13.30 | | | | 0.65 | 8.65 | | |
| 21.2 | 35 | No Work | Cum | 1 | 0.00 | | | | 0.00 | 0.00 | | |
| | | | | | | | | | | | | |
| | | Judicial Layout | | | | | | | | | | |
| | | South Side | | | | | | | | | | |
| | | Top Portion | | | | | | | | | | |
| 0 | 6.5 | | Sqm | 1 | 6.50 | 0.60 | 0.60 | 0.60 | | 3.90 | | |
| | | | | | | | | | | | | |
| | | West Side | | | | | | | | | | |
| 0 | 15 | | Sqm | 1 | 15.00 | 0.60 | 0.60 | 0.60 | | 9.00 | | |
| 15 | 25.65 | | Sqm | 1 | 10.65 | 0.60 | 0.60 | 0.60 | | 6.39 | | |
| | | | | | | | | | | | | |
| | | wall | | | | | | | | | | |
| | | Judicial Layout | | | | | | | | | | |
| | | South Side | | | | | | | | | | |
| 0 | 6.5 | | Sqm | 1 | 6.50 | | | | 0.90 | 5.85 | | |
| | | | | | | | | | | | | |
| | | West Side | | | | | | | | | | |
| 0 | 15 | | Sqm | 2 | 15.00 | | | | 0.90 | 27.00 | | |
| 15 | 25.65 | | Sqm | 2 | 10.65 | | | | 0.90 | 19.17 | | |
| | | | | | | | | | | | | |
| | | 16th B Cross Road | | | | | | | | | | |
| | | Service Road West Side | | | | | | | | | | |
| 0 | 15 | | Sqm | 1 | 15.00 | 0.50 | 0.50 | 0.50 | | 7.50 | | |
| 15 | 30 | | Sqm | 1 | 15.00 | 0.50 | 0.50 | 0.50 | | 7.50 | | |
| 30 | 45 | | Sqm | 1 | 15.00 | 0.50 | 0.50 | 0.50 | | 7.50 | | |
| 45 | 60 | | Sqm | 1 | 15.00 | 0.50 | 0.50 | 0.50 | | 7.50 | | |
| 60 | 75 | | Sqm | 1 | 15.00 | 0.50 | 0.50 | 0.50 | | 7.50 | | |
| 75 | 90 | | Sqm | 1 | 15.00 | 0.50 | 0.50 | 0.50 | | 7.50 | | |
| 90 | 105 | | Sqm | 1 | 15.00 | 0.50 | 0.50 | 0.50 | | 7.50 | | |
| 105 | 107.1 | | Sqm | 1 | 2.10 | 0.50 | 0.50 | 0.50 | | 1.05 | | |
| | | | | | | | | | | | | |
| | | North Side | | | | | | | | | | |
| 0 | 5.4 | | Sqm | 1 | 5.40 | 0.50 | 0.50 | 0.50 | | 2.70 | | |
| | | | | | | | | | | | | |
| | | South Side | | | | | | | | | | |
| 0 | 5.5 | | Sqm | 1 | 5.50 | 0.50 | 0.50 | 0.50 | | 2.75 | | |
| | | | | | | | | | | | | |
| | | East Side | | | | | | | | | | |
| 0 | 2.5 | Gate | Sqm | 1 | 0.00 | 0.50 | 0.50 | 0.50 | | 0.00 | | |
| 2.5 | 17.5 | | Sqm | 1 | 15.00 | 0.50 | 0.50 | 0.50 | | 7.50 | | |

| Chainage | | Description of Item | Unit | No | Length | Breadth | | | Depth | Qty | Rate | Amount |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| From | To | | | | | B1 | B2 | Avg | | | | |
| 17.5 | 32.5 | | Sqm | 1 | 15.00 | 0.50 | 0.50 | 0.50 | | 7.50 | | |
| 32.5 | 47.5 | | Sqm | 1 | 15.00 | 0.50 | 0.50 | 0.50 | | 7.50 | | |
| 47.5 | 62.5 | | Sqm | 1 | 15.00 | 0.50 | 0.50 | 0.50 | | 7.50 | | |
| 62.5 | 77.5 | | Sqm | 1 | 15.00 | 0.50 | 0.50 | 0.50 | | 7.50 | | |
| 77.5 | 92.5 | | Sqm | 1 | 15.00 | 0.50 | 0.50 | 0.50 | | 7.50 | | |
| 92.5 | 103.5 | | Sqm | 1 | 11.00 | 0.50 | 0.50 | 0.50 | | 5.50 | | |
| 103.5 | 105.7 | Gate | Sqm | 1 | 0.00 | 0.50 | 0.50 | 0.50 | | 0.00 | | |
| | | | | | | | | | | | | |
| | | Wall | | | | | | | | | | |
| | | 16th B Cross Road | | | | | | | | | | |
| | | Service Road West Side | | | | | | | | | | |
| 0 | 15 | | Sqm | 2 | 15.00 | | | | 0.50 | 15.00 | | |
| 15 | 30 | | Sqm | 2 | 15.00 | | | | 0.50 | 15.00 | | |
| 30 | 45 | | Sqm | 2 | 15.00 | | | | 0.50 | 15.00 | | |
| 45 | 60 | | Sqm | 2 | 15.00 | | | | 0.50 | 15.00 | | |
| 60 | 75 | | Sqm | 2 | 15.00 | | | | 0.50 | 15.00 | | |
| 75 | 90 | | Sqm | 2 | 15.00 | | | | 0.50 | 15.00 | | |
| 90 | 105 | | Sqm | 2 | 15.00 | | | | 0.50 | 15.00 | | |
| 105 | 107.1 | | Sqm | 2 | 2.10 | | | | 0.50 | 2.10 | | |
| | | | | | | | | | | | | |
| | | North Side | | | | | | | | | | |
| 0 | 5.4 | | Sqm | 2 | 5.40 | | | | 0.50 | 5.40 | | |
| | | | | | | | | | | | | |
| | | South Side | | | | | | | | | | |
| 0 | 5.5 | | Sqm | 2 | 5.50 | | | | 0.50 | 5.50 | | |
| | | | | | | | | | | | | |
| | | East Side | | | | | | | | | | |
| 0 | 2.5 | Gate | Sqm | 2 | 0.00 | | | | 0.50 | 0.00 | | |
| 2.5 | 17.5 | | Sqm | 2 | 15.00 | | | | 0.50 | 15.00 | | |
| 17.5 | 32.5 | | Sqm | 2 | 15.00 | | | | 0.50 | 15.00 | | |
| 32.5 | 47.5 | | Sqm | 2 | 15.00 | | | | 0.50 | 15.00 | | |
| 47.5 | 62.5 | | Sqm | 2 | 15.00 | | | | 0.50 | 15.00 | | |
| 62.5 | 77.5 | | Sqm | 2 | 15.00 | | | | 0.50 | 15.00 | | |
| 77.5 | 92.5 | | Sqm | 2 | 15.00 | | | | 0.50 | 15.00 | | |
| 92.5 | 103.5 | | Sqm | 2 | 11.00 | | | | 0.50 | 11.00 | | |
| 103.5 | 105.7 | Gate | Sqm | 2 | 0.00 | | | | 0.50 | 0.00 | | |
| | | | | | | | | | Total | 897.97 | | |
| | | | | | | | | | Tender Quantity | 467.82 | | |
| | | | | | | | | | Quantity Upto 125% | 584.78 | 290.08 | 169632.00 |
| | | | | | | | | | Quantity Above 125% | 313.19 | 290.22 | 90894.00 |
| 13 | | Providing and fixing for flooring 20mm thick gang saw water cut sadarhalli gray granite in CM 1:4 proportion, cut to required shape, pattern with paper joints, finished with cement mortar using white cement and colour pigments to match the colour of slab making through jointing with sealant, groves in joints including cost of curing - minimum width of 1200mm. and as per the directions of the Engineer-in-charge of the work | | | | | | | | | | |
| | | **Parking Lot** | | | | | | | | | | |
| | | **From Bike Parking Lot to Public Toilet** | | | | | | | | | | |
| | | **Top Surface** | | | | | | | | | | |
| 0 | 12.8 | | Sqm | 1 | 12.80 | 1.14 | 1.10 | 1.12 | | 14.34 | | |
| 12.8 | 17.2 | | Sqm | 1 | 4.40 | 0.66 | 0.68 | 0.67 | | 2.95 | | |
| 17.2 | 24.2 | No Work | Sqm | 1 | 0.00 | 0.00 | 0.00 | 0.00 | | 0.00 | | |
| 24.2 | 25.2 | | Sqm | 1 | 1.00 | 0.65 | 0.66 | 0.66 | | 0.66 | | |
| 25.2 | 30.3 | | Sqm | 1 | 5.10 | 0.66 | 0.63 | 0.65 | | 3.29 | | |
| 30.3 | 34.3 | | Sqm | 1 | 4.00 | 1.10 | 1.10 | 1.10 | | 4.40 | | |
| 34.3 | 35.2 | | Sqm | 1 | 0.90 | 0.47 | 0.57 | 0.52 | | 0.47 | | |
| 35.2 | 43.2 | | Sqm | 1 | 8.00 | 1.10 | 1.10 | 1.10 | | 8.80 | | |
| 43.2 | 44.2 | | Sqm | 1 | 1.00 | 0.58 | 0.58 | 0.58 | | 0.58 | | |
| 44.2 | 50.6 | | Sqm | 1 | 6.40 | 1.10 | 1.10 | 1.10 | | 7.04 | | |
| 50.6 | 51.4 | | Sqm | 1 | 0.80 | 0.62 | 0.62 | 0.62 | | 0.50 | | |
| 51.4 | 52.1 | | Sqm | 1 | 0.70 | 1.13 | 1.12 | 1.13 | | 0.79 | | |
| 52.1 | 53 | | Sqm | 1 | 0.90 | 0.55 | 0.55 | 0.55 | | 0.49 | | |

| Chainage | | Description of Item | Unit | No | Length | Breadth | | | Depth | Qty | Rate | Amount |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| From | To | | | | | B1 | B2 | Avg | | | | |
| 53 | 61.1 | | Sqm | 1 | 8.10 | 1.12 | 1.10 | 1.11 | | 8.99 | | |
| 61.1 | 62.2 | | Sqm | 1 | 1.10 | 0.70 | 0.68 | 0.69 | | 0.76 | | |
| 62.2 | 69 | | Sqm | 1 | 6.80 | 1.12 | 1.12 | 1.12 | | 7.62 | | |
| 69 | 70.1 | | Sqm | 1 | 1.10 | 0.58 | 0.61 | 0.60 | | 0.65 | | |
| 70.1 | 78 | | Sqm | 1 | 7.90 | 1.13 | 1.15 | 1.14 | | 9.01 | | |
| 78 | 79 | | Sqm | 1 | 1.00 | 0.53 | 0.53 | 0.53 | | 0.53 | | |
| 79 | 87.2 | | Sqm | 1 | 8.20 | 1.12 | 1.15 | 1.14 | | 9.31 | | |
| 87.2 | 88.1 | | Sqm | 1 | 0.90 | 0.55 | 0.55 | 0.55 | | 0.49 | | |
| 88.1 | 96 | | Sqm | 1 | 7.90 | 1.16 | 1.25 | 1.21 | | 9.52 | | |
| 96 | 97 | | Sqm | 1 | 1.00 | 0.63 | 0.63 | 0.63 | | 0.63 | | |
| 97 | 105 | | Sqm | 1 | 8.00 | 1.25 | 1.20 | 1.23 | | 9.80 | | |
| 105 | 106 | | Sqm | 1 | 1.00 | 0.62 | 0.62 | 0.62 | | 0.62 | | |
| 106 | 114 | | Sqm | 1 | 8.00 | 1.22 | 1.22 | 1.22 | | 9.76 | | |
| 114 | 114.9 | | Sqm | 1 | 0.90 | 0.58 | 0.58 | 0.58 | | 0.52 | | |
| 114.9 | 125.1 | | Sqm | 1 | 10.20 | 1.23 | 1.17 | 1.20 | | 12.24 | | |
| 125.1 | 130.4 | | Sqm | 1 | 5.30 | 0.63 | 0.55 | 0.59 | | 3.13 | | |
| 130.4 | 139.5 | Gate | Sqm | 1 | 0.00 | 0.00 | 0.00 | 0.00 | | 0.00 | | |
| 139.5 | 145.9 | | Sqm | 1 | 6.40 | 0.65 | 0.62 | 0.64 | | 4.06 | | |
| 145.9 | 152.6 | | Sqm | 1 | 6.70 | 1.10 | 1.18 | 1.14 | | 7.64 | | |
| 152.6 | 153.6 | | Sqm | 1 | 1.00 | 0.60 | 0.58 | 0.59 | | 0.59 | | |
| 153.6 | 161.6 | | Sqm | 1 | 8.00 | 1.06 | 1.06 | 1.06 | | 8.48 | | |
| 161.6 | 162.6 | | Sqm | 1 | 1.00 | 0.60 | 0.60 | 0.60 | | 0.60 | | |
| 162.6 | 170.5 | | Sqm | 1 | 7.90 | 1.06 | 1.04 | 1.05 | | 8.30 | | |
| 170.5 | 171.4 | | Sqm | 1 | 0.90 | 0.60 | 0.60 | 0.60 | | 0.54 | | |
| 171.4 | 179 | | Sqm | 1 | 7.60 | 1.04 | 1.03 | 1.04 | | 7.87 | | |
| 179 | 180.5 | | Sqm | 1 | 1.50 | 0.58 | 0.57 | 0.58 | | 0.86 | | |
| 180.5 | 188.4 | | Sqm | 1 | 7.90 | 1.03 | 1.05 | 1.04 | | 8.22 | | |
| 188.4 | 189.5 | | Sqm | 1 | 1.10 | 0.60 | 0.60 | 0.60 | | 0.66 | | |
| 189.5 | 197.4 | | Sqm | 1 | 7.90 | 1.06 | 1.06 | 1.06 | | 8.37 | | |
| 197.4 | 198.4 | | Sqm | 1 | 1.00 | 0.65 | 0.65 | 0.65 | | 0.65 | | |
| 198.4 | 206.4 | | Sqm | 1 | 8.00 | 1.07 | 1.07 | 1.07 | | 8.56 | | |
| 206.4 | 207.3 | | Sqm | 1 | 0.90 | 0.65 | 0.65 | 0.65 | | 0.59 | | |
| 207.3 | 215.3 | | Sqm | 1 | 8.00 | 1.07 | 1.03 | 1.05 | | 8.40 | | |
| 215.3 | 216.3 | | Sqm | 1 | 1.00 | 0.64 | 0.64 | 0.64 | | 0.64 | | |
| 216.3 | 217.6 | | Sqm | 1 | 1.30 | 0.64 | 0.64 | 0.64 | | 0.83 | | |
| 217.6 | 224.2 | | Sqm | 1 | 6.60 | 1.04 | 1.04 | 1.04 | | 6.86 | | |
| 224.2 | 225.2 | | Sqm | 1 | 1.00 | 0.60 | 0.60 | 0.60 | | 0.60 | | |
| 225.2 | 233.1 | | Sqm | 1 | 7.90 | 1.07 | 1.03 | 1.05 | | 8.30 | | |
| 233.1 | 234.1 | | Sqm | 1 | 1.00 | 0.60 | 0.60 | 0.60 | | 0.60 | | |
| 234.1 | 242.1 | | Sqm | 1 | 8.00 | 1.03 | 1.04 | 1.04 | | 8.28 | | |
| 242.1 | 243.3 | | Sqm | 1 | 1.20 | 0.62 | 0.62 | 0.62 | | 0.74 | | |
| 243.3 | 246.7 | | Sqm | 1 | 3.40 | 1.04 | 1.05 | 1.05 | | 3.55 | | |
| 246.7 | 252.4 | | Sqm | 1 | 5.70 | 0.62 | 0.65 | 0.64 | | 3.62 | | |
| 252.4 | 253.2 | | Sqm | 1 | 0.80 | 0.65 | 0.50 | 0.58 | | 0.46 | | |
| 253.2 | 260.4 | Gate | Sqm | 1 | 0.00 | 0.00 | 0.00 | 0.00 | | 0.00 | | |
| 260.4 | 264.4 | | Sqm | 1 | 4.00 | 0.62 | 0.60 | 0.61 | | 2.44 | | |
| 264.4 | 270 | | Sqm | 1 | 5.60 | 1.04 | 1.04 | 1.04 | | 5.82 | | |
| 270 | 281.8 | | Sqm | 1 | 11.80 | 1.04 | 1.04 | 1.04 | | 12.27 | | |
| 281.8 | 283.4 | Gate | Sqm | 1 | 0.00 | 0.00 | 0.00 | 0.00 | | 0.00 | | |
| 283.4 | 290 | | Sqm | 1 | 6.60 | 1.04 | 1.04 | 1.04 | | 6.86 | | |
| 290 | 302.9 | | Sqm | 1 | 12.90 | 1.04 | 1.05 | 1.05 | | 13.48 | | |
| | | | | | | | | | | | | |
| 0 | 0 | Wall Surface | | | | | | | | | | |
| 0 | 12.8 | | Sqm | 1 | 12.80 | | | | 0.48 | 6.08 | | |
| 12.8 | 17.2 | | Sqm | 1 | 4.40 | | | | 0.52 | 2.27 | | |
| 17.2 | 24.2 | No Work | Sqm | 1 | 0.00 | | | | 0.00 | 0.00 | | |
| 24.2 | 25.2 | | Sqm | 1 | 1.00 | | | | 0.71 | 0.71 | | |
| 25.2 | 30.3 | | Sqm | 1 | 5.10 | | | | 0.75 | 3.83 | | |
| 30.3 | 34.3 | | Sqm | 1 | 4.00 | | | | 0.48 | 1.92 | | |
| 34.3 | 35.2 | No Work | Sqm | 1 | 0.00 | | | | 0.00 | 0.00 | | |
| 35.2 | 43.2 | | Sqm | 1 | 8.00 | | | | 0.48 | 3.84 | | |
| 43.2 | 44.2 | No Work | Sqm | 1 | 0.00 | | | | 0.00 | 0.00 | | |

| Chainage | | Description of Item | Unit | No | Length | Breadth | | | Depth | Qty | Rate | Amount |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| From | To | | | | | B1 | B2 | Avg | | | | |
| 44.2 | 50.6 | | Sqm | 1 | 6.40 | | | | 0.47 | 3.01 | | |
| 50.6 | 51.4 | No Work | Sqm | 1 | 0.00 | | | | 0.00 | 0.00 | | |
| 51.4 | 52.1 | | Sqm | 1 | 0.70 | | | | 0.47 | 0.33 | | |
| 52.1 | 53 | No Work | Sqm | 1 | 0.00 | | | | 0.00 | 0.00 | | |
| 53 | 61.1 | | Sqm | 1 | 8.10 | | | | 0.47 | 3.81 | | |
| 61.1 | 62.2 | No Work | Sqm | 1 | 0.00 | | | | 0.00 | 0.00 | | |
| 62.2 | 69 | | Sqm | 1 | 6.80 | | | | 0.47 | 3.20 | | |
| 69 | 70.1 | No Work | Sqm | 1 | 0.00 | | | | 0.00 | 0.00 | | |
| 70.1 | 78 | | Sqm | 1 | 7.90 | | | | 0.48 | 3.75 | | |
| 78 | 79 | No Work | Sqm | 1 | 0.00 | | | | 0.00 | 0.00 | | |
| 79 | 87.2 | | Sqm | 1 | 8.20 | | | | 0.47 | 3.85 | | |
| 87.2 | 88.1 | No Work | Sqm | 1 | 0.00 | | | | 0.00 | 0.00 | | |
| 88.1 | 96 | | Sqm | 1 | 7.90 | | | | 0.47 | 3.67 | | |
| 96 | 97 | No Work | Sqm | 1 | 0.00 | | | | 0.00 | 0.00 | | |
| 97 | 105 | | Sqm | 1 | 8.00 | | | | 0.47 | 3.72 | | |
| 105 | 106 | No Work | Sqm | 1 | 0.00 | | | | 0.00 | 0.00 | | |
| 106 | 114 | | Sqm | 1 | 8.00 | | | | 0.45 | 3.60 | | |
| 114 | 114.9 | No Work | Sqm | 1 | 0.00 | | | | 0.00 | 0.00 | | |
| 114.9 | 125.1 | | Sqm | 1 | 10.20 | | | | 0.46 | 4.64 | | |
| 125.1 | 130.4 | | Sqm | 1 | 5.30 | | | | 0.40 | 2.12 | | |
| 130.4 | 139.5 | Gate | Sqm | 1 | 0.00 | | | | 0.00 | 0.00 | | |
| 139.5 | 145.9 | | Sqm | 1 | 6.40 | | | | 0.63 | 4.03 | | |
| 145.9 | 152.6 | | Sqm | 1 | 6.70 | | | | 0.42 | 2.81 | | |
| 152.6 | 153.6 | No Work | Sqm | 1 | 0.00 | | | | 0.00 | 0.00 | | |
| 153.6 | 161.6 | | Sqm | 1 | 8.00 | | | | 0.45 | 3.60 | | |
| 161.6 | 162.6 | No Work | Sqm | 1 | 0.00 | | | | 0.00 | 0.00 | | |
| 162.6 | 170.5 | | Sqm | 1 | 7.90 | | | | 0.45 | 3.56 | | |
| 170.5 | 171.4 | No Work | Sqm | 1 | 0.00 | | | | 0.00 | 0.00 | | |
| 171.4 | 179 | | Sqm | 1 | 7.60 | | | | 0.45 | 3.38 | | |
| 179 | 180.5 | No Work | Sqm | 1 | 0.00 | | | | 0.00 | 0.00 | | |
| 180.5 | 188.4 | | Sqm | 1 | 7.90 | | | | 0.50 | 3.91 | | |
| 188.4 | 189.5 | No Work | Sqm | 1 | 0.00 | | | | 0.00 | 0.00 | | |
| 189.5 | 197.4 | | Sqm | 1 | 7.90 | | | | 0.49 | 3.83 | | |
| 197.4 | 198.4 | No Work | Sqm | 1 | 0.00 | | | | 0.00 | 0.00 | | |
| 198.4 | 206.4 | | Sqm | 1 | 8.00 | | | | 0.50 | 3.96 | | |
| 206.4 | 207.3 | No Work | Sqm | 1 | 0.00 | | | | 0.00 | 0.00 | | |
| 207.3 | 215.3 | | Sqm | 1 | 8.00 | | | | 0.50 | 3.96 | | |
| 215.3 | 216.3 | No Work | Sqm | 1 | 0.00 | | | | 0.00 | 0.00 | | |
| 216.3 | 217.6 | | Sqm | 1 | 1.30 | | | | 0.50 | 0.65 | | |
| 217.6 | 224.2 | | Sqm | 1 | 6.60 | | | | 0.49 | 3.20 | | |
| 224.2 | 225.2 | | Sqm | 1 | 0.00 | | | | 0.00 | 0.00 | | |
| 225.2 | 233.1 | | Sqm | 1 | 7.90 | | | | 0.46 | 3.63 | | |
| 233.1 | 234.1 | | Sqm | 1 | 0.00 | | | | 0.00 | 0.00 | | |
| 234.1 | 242.1 | | Sqm | 1 | 8.00 | | | | 0.47 | 3.76 | | |
| 242.1 | 243.3 | | Sqm | 1 | 0.00 | | | | 0.00 | 0.00 | | |
| 243.3 | 246.7 | | Sqm | 1 | 3.40 | | | | 0.45 | 1.53 | | |
| 246.7 | 252.4 | | Sqm | 1 | 5.70 | | | | 0.44 | 2.51 | | |
| 252.4 | 253.2 | | Sqm | 1 | 0.80 | | | | 0.40 | 0.32 | | |
| 253.2 | 260.4 | Gate | Sqm | 1 | 0.00 | | | | 0.00 | 0.00 | | |
| 260.4 | 264.4 | | Sqm | 1 | 4.00 | | | | 0.43 | 1.70 | | |
| 264.4 | 270 | | Sqm | 1 | 5.60 | | | | 0.26 | 1.46 | | |
| 270 | 281.8 | | Sqm | 1 | 11.80 | | | | 0.22 | 2.54 | | |
| 281.8 | 283.4 | Gate | Sqm | 1 | 0.00 | | | | 0.00 | 0.00 | | |
| 283.4 | 290 | No Work | Sqm | 1 | 0.00 | | | | 0.00 | 0.00 | | |
| 290 | 302.9 | No Work | Sqm | 1 | 0.00 | | | | 0.00 | 0.00 | | |
| | | | | | | | | | | 0.00 | | |
| | | Side Granite Work | | | | | | | | | | |
| | | | Sqm | 1 | 0.47 | | | | 0.66 | 0.31 | | |
| | | | Sqm | 1 | 0.43 | | | | 0.49 | 0.21 | | |
| | | | Sqm | 1 | 0.63 | | | | 0.52 | 0.33 | | |
| | | | Sqm | 1 | 0.60 | | | | 0.62 | 0.37 | | |
| | | | Sqm | 1 | 0.46 | | | | 0.67 | 0.31 | | |

| Chainage | | Description of Item | Unit | No | Length | Breadth | | | Depth | Qty | Rate | Amount |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| From | To | | | | | B1 | B2 | Avg | | | | |
| | | | Sqm | 2 | 0.25 | | | | 0.48 | 0.24 | | |
| | | | Sqm | 2 | 0.43 | | | | 0.47 | 0.40 | | |
| | | | Sqm | 2 | 0.48 | | | | 0.66 | 0.63 | | |
| | | | Sqm | 2 | 0.21 | | | | 0.46 | 0.19 | | |
| | | | Sqm | 1 | 0.17 | | | | 0.47 | 0.08 | | |
| | | | Sqm | 1 | 0.24 | | | | 0.47 | 0.11 | | |
| | | | Sqm | 2 | 0.20 | | | | 0.47 | 0.19 | | |
| | | | Sqm | 1 | 0.25 | | | | 0.47 | 0.12 | | |
| | | | Sqm | 1 | 0.20 | | | | 0.47 | 0.09 | | |
| | | | Sqm | 1 | 0.25 | | | | 0.47 | 0.12 | | |
| | | | Sqm | 1 | 0.23 | | | | 0.47 | 0.11 | | |
| | | | Sqm | 2 | 0.17 | | | | 0.47 | 0.16 | | |
| | | | Sqm | 1 | 0.20 | | | | 0.47 | 0.09 | | |
| | | | Sqm | 1 | 0.30 | | | | 0.47 | 0.14 | | |
| | | | Sqm | 1 | 0.25 | | | | 0.45 | 0.11 | | |
| | | | Sqm | 1 | 0.30 | | | | 0.45 | 0.14 | | |
| | | | Sqm | 1 | 0.53 | | | | 0.62 | 0.33 | | |
| | | | Sqm | 1 | 0.55 | | | | 0.30 | 0.17 | | |
| | | | Sqm | 1 | 0.45 | | | | 0.60 | 0.27 | | |
| | | | Sqm | 3 | 0.17 | | | | 0.45 | 0.23 | | |
| | | | Sqm | 1 | 0.14 | | | | 0.45 | 0.06 | | |
| | | | Sqm | 2 | 0.09 | | | | 0.45 | 0.08 | | |
| | | | Sqm | 1 | 0.20 | | | | 0.45 | 0.09 | | |
| | | | Sqm | 1 | 0.15 | | | | 0.45 | 0.07 | | |
| | | | Sqm | 1 | 0.17 | | | | 0.50 | 0.09 | | |
| | | | Sqm | 1 | 0.20 | | | | 0.50 | 0.10 | | |
| | | | Sqm | 2 | 0.18 | | | | 0.47 | 0.17 | | |
| | | | Sqm | 2 | 0.20 | | | | 0.50 | 0.20 | | |
| | | | Sqm | 1 | 0.11 | | | | 0.50 | 0.06 | | |
| | | | Sqm | 1 | 0.36 | | | | 0.65 | 0.23 | | |
| | | | Sqm | 2 | 0.16 | | | | 0.47 | 0.15 | | |
| | | | Sqm | 2 | 0.15 | | | | 0.45 | 0.14 | | |
| | | | Sqm | 2 | 0.18 | | | | 0.45 | 0.16 | | |
| | | | Sqm | 1 | 0.40 | | | | 0.50 | 0.20 | | |
| | | | Sqm | 1 | 0.10 | | | | 0.48 | 0.05 | | |
| | | | Sqm | 1 | 0.45 | | | | 0.30 | 0.14 | | |
| | | | Sqm | 1 | 0.58 | | | | 0.30 | 0.17 | | |
| | | | Sqm | 1 | 0.42 | | | | 0.48 | 0.20 | | |
| | | | | | | | | | | | | |
| | | Arch Portions | | | | | | | | | | |
| | | Top Surface | | | | | | | | | | |
| | | | Sqm | 1 | 1.10 | 0.16 | 0.16 | 0.16 | | 0.18 | | |
| | | | Sqm | 1 | 1.10 | 0.16 | 0.16 | 0.16 | | 0.18 | | |
| | | | Sqm | 1 | 1.16 | 0.20 | 0.20 | 0.20 | | 0.23 | | |
| | | | Sqm | 1 | 1.15 | 0.16 | 0.16 | 0.16 | | 0.18 | | |
| | | | Sqm | 1 | 1.15 | 0.22 | 0.22 | 0.22 | | 0.25 | | |
| | | | Sqm | 1 | 1.12 | 0.16 | 0.16 | 0.16 | | 0.18 | | |
| | | | Sqm | 1 | 1.15 | 0.15 | 0.15 | 0.15 | | 0.17 | | |
| | | | Sqm | 1 | 1.05 | 0.15 | 0.15 | 0.15 | | 0.16 | | |
| | | | Sqm | 1 | 1.15 | 0.15 | 0.15 | 0.15 | | 0.17 | | |
| | | | Sqm | 1 | 1.07 | 0.15 | 0.15 | 0.15 | | 0.16 | | |
| | | | Sqm | 1 | 1.08 | 0.15 | 0.15 | 0.15 | | 0.16 | | |
| | | | Sqm | 1 | 1.05 | 0.16 | 0.16 | 0.16 | | 0.17 | | |
| | | | Sqm | 1 | 1.00 | 0.16 | 0.16 | 0.16 | | 0.16 | | |
| | | | Sqm | 1 | 1.05 | 0.15 | 0.15 | 0.15 | | 0.16 | | |
| | | | Sqm | 1 | 1.06 | 0.15 | 0.15 | 0.15 | | 0.16 | | |
| | | | Sqm | 1 | 1.07 | 0.16 | 0.16 | 0.16 | | 0.17 | | |
| | | | Sqm | 1 | 1.07 | 0.13 | 0.13 | 0.13 | | 0.14 | | |
| | | | Sqm | 1 | 1.22 | 0.13 | 0.13 | 0.13 | | 0.16 | | |
| | | | Sqm | 1 | 1.07 | 0.14 | 0.14 | 0.14 | | 0.15 | | |
| | | | Sqm | 1 | 1.04 | 0.15 | 0.15 | 0.15 | | 0.16 | | |
| | | | Sqm | 1 | 1.05 | 0.15 | 0.15 | 0.15 | | 0.16 | | |

| Chainage From | Chainage To | Description of Item | Unit | No | Length | Breadth B1 | Breadth B2 | Breadth Avg | Depth | Qty | Rate | Amount |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | Wall Portion | | | | | | | | | | |
| | | | Sqm | 1 | 1.10 | | | | 0.50 | 0.55 | | |
| | | | Sqm | 1 | 1.10 | | | | 0.47 | 0.52 | | |
| | | | Sqm | 1 | 1.16 | | | | 0.46 | 0.53 | | |
| | | | Sqm | 1 | 1.15 | | | | 0.47 | 0.54 | | |
| | | | Sqm | 1 | 1.15 | | | | 0.47 | 0.54 | | |
| | | | Sqm | 1 | 1.12 | | | | 0.47 | 0.53 | | |
| | | | Sqm | 1 | 1.15 | | | | 0.47 | 0.54 | | |
| | | | Sqm | 1 | 1.05 | | | | 0.45 | 0.47 | | |
| | | | Sqm | 1 | 1.15 | | | | 0.47 | 0.54 | | |
| | | | Sqm | 1 | 1.07 | | | | 0.43 | 0.46 | | |
| | | | Sqm | 1 | 1.08 | | | | 0.45 | 0.49 | | |
| | | | Sqm | 1 | 1.05 | | | | 0.45 | 0.47 | | |
| | | | Sqm | 1 | 1.00 | | | | 0.45 | 0.45 | | |
| | | | Sqm | 1 | 1.05 | | | | 0.50 | 0.53 | | |
| | | | Sqm | 1 | 1.06 | | | | 0.50 | 0.53 | | |
| | | | Sqm | 1 | 1.07 | | | | 0.48 | 0.51 | | |
| | | | Sqm | 1 | 1.07 | | | | 0.54 | 0.58 | | |
| | | | Sqm | 1 | 1.22 | | | | 0.50 | 0.61 | | |
| | | | Sqm | 1 | 1.07 | | | | 0.47 | 0.50 | | |
| | | | Sqm | 1 | 1.04 | | | | 0.48 | 0.50 | | |
| | | | Sqm | 1 | 1.05 | | | | 0.45 | 0.47 | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | Deduction | | | | | | | | | | |
| | | | Sqm | -1 | 0.60 | 0.50 | 0.50 | 0.50 | | -0.30 | | |
| | | | Sqm | -1 | 0.30 | 0.39 | 0.39 | 0.39 | | -0.12 | | |
| | | | | | | | | | Total | 408.14 | 2279.50 | 930366.00 |
| | | | | | | | | | Tender Quantity | 697.00 | | |
| 14 | | Providing half nosing for 20mm thick granite slab using required machinery including cost and conveyance of all materials, labour for all items of work, HOM of equipment etc., complete as per specification and as per the directions of the Engineer-in-charge of the work | | | | | | | | | | |
| | | **Parking Lot** | | | | | | | | | | |
| | | **From Bike Parking Lot to Public Toilet** | | | | | | | | | | |
| | | Top Surface | | | | | | | | | | |
| 0 | 12.8 | | Sqm | 2 | 12.80 | | | | | 25.60 | | |
| 12.8 | 17.2 | | Sqm | 2 | 4.40 | | | | | 8.80 | | |
| 17.2 | 24.2 | No Work | Sqm | 2 | 0.00 | | | | | 0.00 | | |
| 24.2 | 25.2 | | Sqm | 2 | 1.00 | | | | | 2.00 | | |
| 25.2 | 30.3 | | Sqm | 2 | 5.10 | | | | | 10.20 | | |
| 30.3 | 34.3 | | Sqm | 2 | 4.00 | | | | | 8.00 | | |
| 34.3 | 35.2 | | Sqm | 2 | 0.90 | | | | | 1.80 | | |
| 35.2 | 43.2 | | Sqm | 2 | 8.00 | | | | | 16.00 | | |
| 43.2 | 44.2 | | Sqm | 2 | 1.00 | | | | | 2.00 | | |
| 44.2 | 50.6 | | Sqm | 2 | 6.40 | | | | | 12.80 | | |
| 50.6 | 51.4 | | Sqm | 2 | 0.80 | | | | | 1.60 | | |
| 51.4 | 52.1 | | Sqm | 2 | 0.70 | | | | | 1.40 | | |
| 52.1 | 53 | | Sqm | 2 | 0.90 | | | | | 1.80 | | |
| 53 | 61.1 | | Sqm | 2 | 8.10 | | | | | 16.20 | | |
| 61.1 | 62.2 | | Sqm | 2 | 1.10 | | | | | 2.20 | | |
| 62.2 | 69 | | Sqm | 2 | 6.80 | | | | | 13.60 | | |
| 69 | 70.1 | | Sqm | 2 | 1.10 | | | | | 2.20 | | |
| 70.1 | 78 | | Sqm | 2 | 7.90 | | | | | 15.80 | | |
| 78 | 79 | | Sqm | 2 | 1.00 | | | | | 2.00 | | |
| 79 | 87.2 | | Sqm | 2 | 8.20 | | | | | 16.40 | | |
| 87.2 | 88.1 | | Sqm | 2 | 0.90 | | | | | 1.80 | | |
| 88.1 | 96 | | Sqm | 2 | 7.90 | | | | | 15.80 | | |
| 96 | 97 | | Sqm | 2 | 1.00 | | | | | 2.00 | | |
| 97 | 105 | | Sqm | 2 | 8.00 | | | | | 16.00 | | |
| 105 | 106 | | Sqm | 2 | 1.00 | | | | | 2.00 | | |

| Chainage | | Description of Item | Unit | No | Length | Breadth | | | Depth | Qty | Rate | Amount |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| From | To | | | | | B1 | B2 | Avg | | | | |
| 106 | 114 | | Sqm | 2 | 8.00 | | | | | 16.00 | | |
| 114 | 114.9 | | Sqm | 2 | 0.90 | | | | | 1.80 | | |
| 114.9 | 125.1 | | Sqm | 2 | 10.20 | | | | | 20.40 | | |
| 125.1 | 130.4 | | Sqm | 2 | 5.30 | | | | | 10.60 | | |
| 130.4 | 139.5 | Gate | Sqm | 2 | 0.00 | | | | | 0.00 | | |
| 139.5 | 145.9 | | Sqm | 2 | 6.40 | | | | | 12.80 | | |
| 145.9 | 152.6 | | Sqm | 2 | 6.70 | | | | | 13.40 | | |
| 152.6 | 153.6 | | Sqm | 2 | 1.00 | | | | | 2.00 | | |
| 153.6 | 161.6 | | Sqm | 2 | 8.00 | | | | | 16.00 | | |
| 161.6 | 162.6 | | Sqm | 2 | 1.00 | | | | | 2.00 | | |
| 162.6 | 170.5 | | Sqm | 2 | 7.90 | | | | | 15.80 | | |
| 170.5 | 171.4 | | Sqm | 2 | 0.90 | | | | | 1.80 | | |
| 171.4 | 179 | | Sqm | 2 | 7.60 | | | | | 15.20 | | |
| 179 | 180.5 | | Sqm | 2 | 1.50 | | | | | 3.00 | | |
| 180.5 | 188.4 | | Sqm | 2 | 7.90 | | | | | 15.80 | | |
| 188.4 | 189.5 | | Sqm | 2 | 1.10 | | | | | 2.20 | | |
| 189.5 | 197.4 | | Sqm | 2 | 7.90 | | | | | 15.80 | | |
| 197.4 | 198.4 | | Sqm | 2 | 1.00 | | | | | 2.00 | | |
| 198.4 | 206.4 | | Sqm | 2 | 8.00 | | | | | 16.00 | | |
| 206.4 | 207.3 | | Sqm | 2 | 0.90 | | | | | 1.80 | | |
| 207.3 | 215.3 | | Sqm | 2 | 8.00 | | | | | 16.00 | | |
| 215.3 | 216.3 | | Sqm | 2 | 1.00 | | | | | 2.00 | | |
| 216.3 | 217.6 | | Sqm | 2 | 1.30 | | | | | 2.60 | | |
| 217.6 | 224.2 | | Sqm | 2 | 6.60 | | | | | 13.20 | | |
| 224.2 | 225.2 | | Sqm | 2 | 1.00 | | | | | 2.00 | | |
| 225.2 | 233.1 | | Sqm | 2 | 7.90 | | | | | 15.80 | | |
| 233.1 | 234.1 | | Sqm | 2 | 1.00 | | | | | 2.00 | | |
| 234.1 | 242.1 | | Sqm | 2 | 8.00 | | | | | 16.00 | | |
| 242.1 | 243.3 | | Sqm | 2 | 1.20 | | | | | 2.40 | | |
| 243.3 | 246.7 | | Sqm | 2 | 3.40 | | | | | 6.80 | | |
| 246.7 | 252.4 | | Sqm | 2 | 5.70 | | | | | 11.40 | | |
| 252.4 | 253.2 | | Sqm | 2 | 0.80 | | | | | 1.60 | | |
| 253.2 | 260.4 | Gate | Sqm | 2 | 0.00 | | | | | 0.00 | | |
| 260.4 | 264.4 | | Sqm | 2 | 4.00 | | | | | 8.00 | | |
| 264.4 | 270 | | Sqm | 2 | 5.60 | | | | | 11.20 | | |
| 270 | 281.8 | | Sqm | 2 | 11.80 | | | | | 23.60 | | |
| 281.8 | 283.4 | Gate | Sqm | 2 | 0.00 | | | | | 0.00 | | |
| 283.4 | 290 | | Sqm | 2 | 6.60 | | | | | 13.20 | | |
| 290 | 302.9 | | Sqm | 2 | 12.90 | | | | | 25.80 | | |
| | | | | | | | | | Total | 556.00 | 203.83 | 113330.00 |
| | | | | | | | | | Tender Quantity | 1040.95 | | |
| 15 | | Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation etc.,complete. and as per the directions of the Engineer-in-charge of the work | | | | | | | | | | |
| | | **Parking Lot** | | | | | | | | | | |
| 0 | 15 | | m | 1 | 15.00 | | | | | 15.00 | | |
| 15 | 19.8 | | m | 1 | 4.80 | | | | | 4.80 | | |
| 19.8 | 21.3 | No Work | m | 1 | 0.00 | | | | | 0.00 | | |
| 21.3 | 36.3 | | m | 1 | 15.00 | | | | | 15.00 | | |
| 36.3 | 38.9 | | m | 1 | 2.60 | | | | | 2.60 | | |
| 38.9 | 56.3 | No Work | m | 1 | 0.00 | | | | | 0.00 | | |
| 56.3 | 71.3 | | m | 1 | 15.00 | | | | | 15.00 | | |
| 71.3 | 85.3 | | m | 1 | 14.00 | | | | | 14.00 | | |
| 85.3 | 86.6 | No Work | m | 1 | 0.00 | | | | | 0.00 | | |
| 86.6 | 101.6 | | m | 1 | 15.00 | | | | | 15.00 | | |
| 101.6 | 117.8 | | m | 1 | 16.20 | | | | | 16.20 | | |
| 117.8 | 118.6 | No Work | m | 1 | 0.00 | | | | | 0.00 | | |
| 118.6 | 133.6 | | m | 1 | 15.00 | | | | | 15.00 | | |
| 133.6 | 148.6 | | m | 1 | 15.00 | | | | | 15.00 | | |
| 148.6 | 157.6 | | m | 1 | 9.00 | | | | | 9.00 | | |
| 157.6 | 178.6 | No Work | m | 1 | 0.00 | | | | | 0.00 | | |

| Chainage | | Description of Item | Unit | No | Length | Breadth | | | Depth | Qty | Rate | Amount |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| From | To | | | | | B1 | B2 | Avg | | | | |
| 178.6 | 193.6 | | m | 1 | 15.00 | | | | | 15.00 | | |
| 193.6 | 203.8 | | m | 1 | 10.20 | | | | | 10.20 | | |
| 203.8 | 206 | No Work | m | 1 | 0.00 | | | | | 0.00 | | |
| 206 | 221 | | m | 1 | 15.00 | | | | | 15.00 | | |
| 221 | 236 | | m | 1 | 15.00 | | | | | 15.00 | | |
| 236 | 252 | | m | 1 | 16.00 | | | | | 16.00 | | |
| 252 | 253 | No Work | m | 1 | 0.00 | | | | | 0.00 | | |
| 253 | 268 | | m | 1 | 15.00 | | | | | 15.00 | | |
| 268 | 273.2 | | m | 1 | 5.20 | | | | | 5.20 | | |
| 273.2 | 291.2 | No Work | m | 1 | 0.00 | | | | | 0.00 | | |
| 291.2 | 299.5 | | m | 1 | 8.30 | | | | | 8.30 | | |
| 299.5 | 301.7 | No Work | m | 1 | 0.00 | | | | | 0.00 | | |
| 301.7 | 304 | | m | 1 | 2.30 | | | | | 2.30 | | |
| | | Total length | | | | | | | | 238.60 | | |
| | | No of Kerb Stones | | | | | | | Total Length/0.45 | 531.00 | | |
| | | **Sub Total** | | | | | | | | **531.00** | | |
| | | | | | | | | | **Total** | **531.00** | **453.46** | **240788.00** |
| | | | | | | | | | **Tender Quantity** | **644.00** | | |
| 16 | | Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications. and as per the directions of the Engineer-in-charge of the work | | | | | | | | | | |
| | | **For Kerb Painting** | | | | | | | | | | |
| | | **Parking Lot** | | | | | | | | | | |
| 0 | 15 | | Sqm | 1 | 15.00 | | | | 0.40 | 6.00 | | |
| 15 | 19.8 | | Sqm | 1 | 4.80 | | | | 0.40 | 1.92 | | |
| 19.8 | 21.3 | No Work | Sqm | 1 | 0.00 | | | | 0.40 | 0.00 | | |
| 21.3 | 36.3 | | Sqm | 1 | 15.00 | | | | 0.40 | 6.00 | | |
| 36.3 | 38.9 | | Sqm | 1 | 2.60 | | | | 0.40 | 1.04 | | |
| 38.9 | 56.3 | No Work | Sqm | 1 | 0.00 | | | | 0.40 | 0.00 | | |
| 56.3 | 71.3 | | Sqm | 1 | 15.00 | | | | 0.40 | 6.00 | | |
| 71.3 | 85.3 | | Sqm | 1 | 14.00 | | | | 0.40 | 5.60 | | |
| 85.3 | 86.6 | No Work | Sqm | 1 | 0.00 | | | | 0.40 | 0.00 | | |
| 86.6 | 101.6 | | Sqm | 1 | 15.00 | | | | 0.40 | 6.00 | | |
| 101.6 | 117.8 | | Sqm | 1 | 16.20 | | | | 0.40 | 6.48 | | |
| 117.8 | 118.6 | No Work | Sqm | 1 | 0.00 | | | | 0.40 | 0.00 | | |
| 118.6 | 133.6 | | Sqm | 1 | 15.00 | | | | 0.40 | 6.00 | | |
| 133.6 | 148.6 | | Sqm | 1 | 15.00 | | | | 0.40 | 6.00 | | |
| 148.6 | 157.6 | | Sqm | 1 | 9.00 | | | | 0.40 | 3.60 | | |
| 157.6 | 178.6 | No Work | Sqm | 1 | 0.00 | | | | 0.40 | 0.00 | | |
| 178.6 | 193.6 | | Sqm | 1 | 15.00 | | | | 0.40 | 6.00 | | |
| 193.6 | 203.8 | | Sqm | 1 | 10.20 | | | | 0.40 | 4.08 | | |
| 203.8 | 206 | No Work | Sqm | 1 | 0.00 | | | | 0.40 | 0.00 | | |
| 206 | 221 | | Sqm | 1 | 15.00 | | | | 0.40 | 6.00 | | |
| 221 | 236 | | Sqm | 1 | 15.00 | | | | 0.40 | 6.00 | | |
| 236 | 252 | | Sqm | 1 | 16.00 | | | | 0.40 | 6.40 | | |
| 252 | 253 | No Work | Sqm | 1 | 0.00 | | | | 0.40 | 0.00 | | |
| 253 | 268 | | Sqm | 1 | 15.00 | | | | 0.40 | 6.00 | | |
| 268 | 273.2 | | Sqm | 1 | 5.20 | | | | 0.40 | 2.08 | | |
| 273.2 | 291.2 | No Work | Sqm | 1 | 0.00 | | | | 0.40 | 0.00 | | |
| 291.2 | 299.5 | | Sqm | 1 | 8.30 | | | | 0.40 | 3.32 | | |
| 299.5 | 301.7 | No Work | Sqm | 1 | 0.00 | | | | 0.40 | 0.00 | | |
| 301.7 | 304 | | Sqm | 1 | 2.30 | | | | 0.40 | 0.92 | | |
| | | | | | | | | | | | | |
| | | SSm Wall Painting | | | | | | | | | | |
| | | Parking Lot | | | | | | | | | | |
| | | Doddaballapura Main Road Side | | | | | | | | | | |
| | | RHS | | | | | | | | | | |
| 0 | 15 | | Sqm | 1 | 15.00 | 0.90 | 1.07 | 0.99 | | 14.78 | | |
| 15 | 30 | | Sqm | 1 | 15.00 | 1.07 | 1.12 | 1.10 | | 16.43 | | |
| 30 | 45 | | Sqm | 1 | 15.00 | 1.12 | 1.20 | 1.16 | | 17.40 | | |

| Chainage From | Chainage To | Description of Item | Unit | No | Length | Breadth B1 | Breadth B2 | Breadth Avg | Depth | Qty | Rate | Amount |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 45 | 60 | | Sqm | 1 | 15.00 | 1.20 | 1.25 | 1.23 | | 18.38 | | |
| 60 | 75 | | Sqm | 1 | 15.00 | 1.25 | 1.00 | 1.13 | | 16.88 | | |
| 75 | 90 | | Sqm | 1 | 15.00 | 1.00 | 1.20 | 1.10 | | 16.50 | | |
| 90 | 105 | | Sqm | 1 | 15.00 | 1.20 | 1.20 | 1.20 | | 18.00 | | |
| 105 | 120 | | Sqm | 1 | 15.00 | 1.20 | 1.10 | 1.15 | | 17.25 | | |
| 120 | 135 | | Sqm | 1 | 15.00 | 1.10 | 1.22 | 1.16 | | 17.40 | | |
| 135 | 150 | | Sqm | 1 | 15.00 | 1.22 | 1.28 | 1.25 | | 18.75 | | |
| 150 | 165 | | Sqm | 1 | 15.00 | 1.28 | 1.15 | 1.22 | | 18.23 | | |
| 165 | 180 | | Sqm | 1 | 15.00 | 1.15 | 1.15 | 1.15 | | 17.25 | | |
| 180 | 195 | | Sqm | 1 | 15.00 | 1.15 | 1.14 | 1.15 | | 17.18 | | |
| 195 | 210 | | Sqm | 1 | 15.00 | 1.14 | 1.17 | 1.16 | | 17.33 | | |
| 210 | 225 | | Sqm | 1 | 15.00 | 1.17 | 1.15 | 1.16 | | 17.40 | | |
| 225 | 240 | | Sqm | 1 | 15.00 | 1.15 | 1.15 | 1.15 | | 17.25 | | |
| 240 | 255 | | Sqm | 1 | 15.00 | 1.15 | 1.25 | 1.20 | | 18.00 | | |
| 255 | 270 | | Sqm | 1 | 15.00 | 1.25 | 1.18 | 1.22 | | 18.23 | | |
| 270 | 275.7 | | Sqm | 1 | 5.70 | 1.18 | 1.18 | 1.18 | | 6.73 | | |
| | | | | | | | | | Total | 414.77 | | |
| | | | | | | | | | Tender Quantity | 115.76 | | |
| | | | | | | | | | Quantity Upto 125% | 144.70 | 88.91 | 12866.00 |
| | | | | | | | | | Quantity Above 125% | 270.07 | 88.96 | 24024.00 |
| 17 | | Construction of Embankment with Material Gravel/ Murrum. KSRRB M300-53. Construction of embankment with approved material Gravel/Murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement Table 300- 2 complete as per specifications.(Including cost of gravel / murrum, watering charges & compaction by vibratory roller to 95% of proctors density and as per the directions of the Engineer-in-charge of the work | | | | | | | | | | |
| | | Parking Lot | | | | | | | | | | |
| | | From Public Toilet To Bike parking | | | | | | | | | | |
| 0.00 | 15.00 | | Sqm | 1 | 15.00 | 0.25 | 0.25 | 0.25 | 0.70 | 2.63 | | |
| 15.00 | 19.40 | | Sqm | 1 | 4.40 | 0.25 | 0.25 | 0.25 | 0.70 | 0.77 | | |
| 19.40 | 21.20 | No Work | Sqm | 1 | 0.00 | 0.25 | 0.25 | 0.25 | 0.70 | 0.00 | | |
| 21.20 | 30.00 | | Sqm | 1 | 8.80 | 0.25 | 0.25 | 0.25 | 0.70 | 1.54 | | |
| 30.00 | 38.70 | | Sqm | 1 | 8.70 | 0.25 | 0.25 | 0.25 | 0.70 | 1.52 | | |
| 38.70 | 56.00 | No Work | Sqm | 1 | 0.00 | 0.25 | 0.25 | 0.25 | 0.70 | 0.00 | | |
| 56.00 | 60.00 | | Sqm | 1 | 4.00 | 0.25 | 0.25 | 0.25 | 0.70 | 0.70 | | |
| 60.00 | 75.00 | | Sqm | 1 | 15.00 | 0.25 | 0.25 | 0.25 | 0.70 | 2.63 | | |
| 75.00 | 84.70 | | Sqm | 1 | 9.70 | 0.25 | 0.25 | 0.25 | 0.70 | 1.70 | | |
| 84.70 | 86.30 | No Work | Sqm | 1 | 0.00 | 0.25 | 0.25 | 0.25 | 0.70 | 0.00 | | |
| 86.30 | 90.00 | | Sqm | 1 | 3.70 | 0.25 | 0.25 | 0.25 | 0.70 | 0.65 | | |
| 90.00 | 105.00 | | Sqm | 1 | 15.00 | 0.25 | 0.25 | 0.25 | 0.70 | 2.63 | | |
| 105.00 | 120.00 | | Sqm | 1 | 15.00 | 0.25 | 0.25 | 0.25 | 0.70 | 2.63 | | |
| 120.00 | 135.00 | | Sqm | 1 | 15.00 | 0.25 | 0.25 | 0.25 | 0.70 | 2.63 | | |
| 135.00 | 150.00 | | Sqm | 1 | 15.00 | 0.25 | 0.25 | 0.25 | 0.70 | 2.63 | | |
| 150.00 | 156.30 | | Sqm | 1 | 6.30 | 0.25 | 0.25 | 0.25 | 0.70 | 1.10 | | |
| 156.30 | 177.10 | No Work | Sqm | 1 | 0.00 | 0.25 | 0.25 | 0.25 | 0.70 | 0.00 | | |
| 177.10 | 185.00 | | Sqm | 1 | 7.90 | 0.25 | 0.25 | 0.25 | 0.70 | 1.38 | | |
| 185.00 | 195.00 | | Sqm | 1 | 10.00 | 0.25 | 0.25 | 0.25 | 0.70 | 1.75 | | |
| 195.00 | 210.00 | | Sqm | 1 | 15.00 | 0.25 | 0.25 | 0.25 | 0.70 | 2.63 | | |
| 210.00 | 225.00 | | Sqm | 1 | 15.00 | 0.25 | 0.25 | 0.25 | 0.70 | 2.63 | | |
| 225.00 | 240.00 | | Sqm | 1 | 15.00 | 0.25 | 0.25 | 0.25 | 0.70 | 2.63 | | |
| 240.00 | 255.00 | | Sqm | 1 | 15.00 | 0.25 | 0.25 | 0.25 | 0.70 | 2.63 | | |
| 255.00 | 261.30 | No Work | Sqm | 1 | 0.00 | 0.25 | 0.25 | 0.25 | 0.70 | 0.00 | | |
| 261.30 | 271.50 | | Sqm | 1 | 10.20 | 0.25 | 0.25 | 0.25 | 0.70 | 1.79 | | |
| 271.50 | 289.30 | No Work | Sqm | 1 | 0.00 | 0.25 | 0.25 | 0.25 | 0.70 | 0.00 | | |
| 289.30 | 302.20 | | Sqm | 1 | 12.90 | 0.25 | 0.25 | 0.25 | 0.70 | 2.26 | | |
| | | | | | | | | | | | | |
| | | 16th 'B' Cross Road | | | | | | | | | | |
| 0.00 | 15.00 | | Sqm | 1 | 15.00 | 5.95 | 5.95 | 5.95 | 0.30 | 26.78 | | |
| 15.00 | 30.00 | | Sqm | 1 | 15.00 | 5.95 | 5.95 | 5.95 | 0.30 | 26.78 | | |
| 30.00 | 37.60 | | Sqm | 1 | 7.60 | 5.95 | 5.95 | 5.95 | 0.30 | 13.57 | | |
| | | | | | | | | | | | | |
| | | Deduction | | | | | | | | | | |

| Chainage From | Chainage To | Description of Item | Unit | No | Length | Breadth B1 | Breadth B2 | Breadth Avg | Depth | Qty | Rate | Amount |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | Sqm | -1 | 2.10 | 1.90 | 1.90 | 1.90 | 0.30 | -1.20 | | |
| | | | | | | | | | Total | 107.32 | 361.21 | 38767.00 |
| | | | | | | | | | Tender Quantity | 119.34 | | |
| 18 | | Construction of partition wall 10 cms thick with table moulded modular burnt bricks of class designation 5.0Newton per sqmm with cement mortar 1:4 including providing and fixing plaster mesh manufactured out of hot dipped galvanised iron of nominal thickness 0.35 mm. 100 mm. wide as per I.S. 2212/1991 at 7.5 m. c to c including cost of materials, labour charges, scaffolding, curing complete as per specifications. and as per the directions of the Engineer-in-charge of the work | | | | | | | | | | |
| | | Arch Portions | | | | | | | | | | |
| | | | Sqm | 1 | 1.20 | | | | 0.80 | 0.96 | | |
| | | | Sqm | 1 | 1.20 | | | | 0.80 | 0.96 | | |
| | | | Sqm | 1 | 1.20 | | | | 0.80 | 0.96 | | |
| | | | Sqm | 1 | 1.20 | | | | 0.80 | 0.96 | | |
| | | | Sqm | 1 | 1.20 | | | | 0.80 | 0.96 | | |
| | | | Sqm | 1 | 1.20 | | | | 0.80 | 0.96 | | |
| | | | Sqm | 1 | 1.20 | | | | 0.80 | 0.96 | | |
| | | | Sqm | 1 | 1.20 | | | | 0.80 | 0.96 | | |
| | | | Sqm | 1 | 1.20 | | | | 0.80 | 0.96 | | |
| | | | Sqm | 1 | 1.20 | | | | 0.80 | 0.96 | | |
| | | | Sqm | 1 | 1.20 | | | | 0.80 | 0.96 | | |
| | | | Sqm | 1 | 1.20 | | | | 0.80 | 0.96 | | |
| | | | Sqm | 1 | 1.20 | | | | 0.80 | 0.96 | | |
| | | | Sqm | 1 | 1.20 | | | | 0.80 | 0.96 | | |
| | | | Sqm | 1 | 1.20 | | | | 0.80 | 0.96 | | |
| | | | Sqm | 1 | 1.20 | | | | 0.80 | 0.96 | | |
| | | | Sqm | 1 | 1.20 | | | | 0.80 | 0.96 | | |
| | | | Sqm | 1 | 1.20 | | | | 0.80 | 0.96 | | |
| | | | Sqm | 1 | 1.20 | | | | 0.80 | 0.96 | | |
| | | | Sqm | 1 | 1.20 | | | | 0.80 | 0.96 | | |
| | | | Sqm | 1 | 1.20 | | | | 0.80 | 0.96 | | |
| | | | Sqm | 1 | 1.20 | | | | 0.80 | 0.96 | | |
| | | | Sqm | 1 | 1.20 | | | | 0.80 | 0.96 | | |
| | | | Sqm | 1 | 1.20 | | | | 0.80 | 0.96 | | |
| | | | | | | | | | Total | 20.16 | | |
| | | | | | | | | | Tender Quantity | 12.85 | | |
| | | | | | | | | | Quantity Upto 125% | 16.06 | 913.58 | 14669.00 |
| | | | | | | | | | Quantity Above 125% | 4.10 | 914.01 | 3751.00 |
| 19 | | Filling in foundation with granite/trap broken metal 100mm and down size ,with approved sand including hand packing, ramming, watering, including cost of all materials and labour with lead up to 50m and lift 1.5m complete as per specifications. and as per the directions of the Engineer-in-charge of the work 40mm Jelly | | | | | | | | | | |
| | | | Cum | 20 | 0.30 | 0.30 | | | 0.40 | 0.72 | | |
| | | Total | | | | | | | | 0.72 | 1993.20 | 1436.00 |
| 20 | | Filling in foundation with granite/trap broken metal 100mm and down size ,with approved sand including hand packing, ramming, watering, including cost of all materials and labour with lead up to 50m and lift 1.5m complete as per specifications. and as per the directions of the Engineer-in-charge of the work 20mm Jelly | | | | | | | | | | |
| | | | Cum | 20 | 0.30 | 0.30 | | | 0.40 | 0.72 | | |
| | | Total | | | | | | | | 0.72 | 1993.20 | 1436.00 |
| 21 | | Filling in foundation with granite/trap broken metal 100mm and down size ,with approved sand including hand packing, ramming, watering, including cost of all materials and labour with lead up to 50m and lift 1.5m complete as per specifications. and as per the directions of the Engineer-in-charge of the work Coarse sand | | | | | | | | | | |
| | | | Cum | 20 | 0.30 | 0.30 | | | 0.30 | 0.54 | | |
| | | Total | | | | | | | | 0.54 | 2779.57 | 1501.00 |
| 22 | | Filling in foundation with granite/trap broken metal 100mm and down size ,with approved sand including hand packing, ramming, watering, including cost of all materials and labour with lead up to 50m and lift 1.5m complete as per specifications. and as per the directions of the Engineer-in-charge of the work Fine sand | | | | | | | | | | |
| | | | Cum | 20 | 0.30 | 0.30 | | | 0.20 | 0.36 | | |
| | | Total | | | | | | | | 0.36 | 2779.57 | 1001.00 |
| 23 | | Filling in foundation with granite/trap broken metal 100mm and down size ,with approved sand including hand packing, ramming, watering, including cost of all materials and labour with lead up to 50m and lift 1.5m complete as per specifications. and as per the directions of the Engineer-in-charge of the work 12.5mm chips | | | | | | | | | | |
| | | | Cum | 20 | 0.30 | 0.30 | | | 0.30 | 0.54 | | |
| | | Total | | | | | | | | 0.54 | 1993.20 | 1077.00 |

| Chainage From | Chainage To | Description of Item | Unit | No | Length | Breadth B1 | Breadth B2 | Breadth Avg | Depth | Qty | Rate | Amount |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 24 | | Supplying, laying and jointing HDPE pipes of specified grade and conforming to IS 4984-995 with latest amendments and conveying to work site including loading at both destinations and rolling and lowering into trenches, laying true to line and jointing of pipes and specials, giving hydraulic test as per relevant ISS with all lead and lifts including encasing the pipe alround to a depth of not less than 15 cms. with soft gravel or selected earth available from the excavation, testing and commissioning. The rate is exclusive of required specials and fittings wherever necessary like saddle tee, stud ends, flanged sets, bends, reducers etc. complete and as per the directions of the Engineer-in-charge of the work | | | | | | | | | | |
| | | 0.1dia HDPE Perforated Pipe. | Rmt | 20 | 2.00 | | | | | 40.00 | | |
| | | | | | | | | | Total | 40.00 | 11347.20 | 453888.00 |
| | | | | | | | | | Tender Quantity | 40.00 | | |
| 25 | | Providing of Geonets for Rain Water Harvesting pit on the filter media as specified in drawings and as per the directions of the Engineer-in-charge of the work | | | | | | | | | | |
| | | | Sqm | 20 | 0.30 | 0.30 | | | | 1.80 | | |
| | | | | | | | | | Total | 1.80 | 74.47 | 135.00 |
| | | | | | | | | | Tender Quantity | 1.80 | | |
| 26 | | Providing and laying heavy duty cobble stones 75mm thick interlock pavers, using cement and course sand for manufacture of blocks of approved size, shape and colour with a minimum compressive strength of 281 kg per sqm over 50mm thick sand bed (average thickness ) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level, including cost of materials, labour and HOM of machineries complete as per specifications. and as per the directions of the Engineer-in-charge of the work | | | | | | | | | | |
| | | Parking Lot | | | | | | | | | | |
| | | Car Parking | | | | | | | | | | |
| 0 | 15 | | Sqm | 1 | 15.00 | 7.50 | 8.65 | 8.08 | | 121.13 | | |
| 15 | 30 | | Sqm | 1 | 15.00 | 8.65 | 8.55 | 8.60 | | 129.00 | | |
| 30 | 45 | | Sqm | 1 | 15.00 | 8.55 | 8.55 | 8.55 | | 128.25 | | |
| 45 | 60 | | Sqm | 1 | 15.00 | 8.55 | 8.55 | 8.55 | | 128.25 | | |
| 60 | 75 | | Sqm | 1 | 15.00 | 8.55 | 8.40 | 8.48 | | 127.13 | | |
| 75 | 90 | | Sqm | 1 | 15.00 | 8.40 | 8.40 | 8.40 | | 126.00 | | |
| 90 | 105 | | Sqm | 1 | 15.00 | 8.40 | 8.30 | 8.35 | | 125.25 | | |
| 105 | 120 | | Sqm | 1 | 15.00 | 8.30 | 8.35 | 8.33 | | 124.88 | | |
| 120 | 135 | | Sqm | 1 | 15.00 | 8.35 | 8.35 | 8.35 | | 125.25 | | |
| 135 | 150 | | Sqm | 1 | 15.00 | 8.35 | 8.30 | 8.33 | | 124.88 | | |
| 150 | 165 | | Sqm | 1 | 15.00 | 8.30 | 8.30 | 8.30 | | 124.50 | | |
| 165 | 180 | | Sqm | 1 | 15.00 | 8.30 | 8.40 | 8.35 | | 125.25 | | |
| 180 | 195 | | Sqm | 1 | 15.00 | 8.40 | 9.30 | 8.85 | | 132.75 | | |
| 195 | 210 | | Sqm | 1 | 15.00 | 9.30 | 9.35 | 9.33 | | 139.88 | | |
| 210 | 215 | | Sqm | 1 | 5.00 | 9.35 | 9.40 | 9.38 | | 46.88 | | |
| 215 | 230 | | Sqm | 1 | 15.00 | 9.40 | 9.30 | 9.35 | | 140.25 | | |
| 230 | 238.2 | | Sqm | 1 | 8.20 | 9.30 | 8.25 | 8.78 | | 71.95 | | |
| | | Bike Parking-Near Temple | | | | | | | | | | |
| 0 | 15 | | Sqm | 1 | 15.00 | 8.40 | 8.35 | 8.38 | | 125.63 | | |
| 15 | 20.3 | | Sqm | 1 | 5.30 | 8.35 | 8.40 | 8.38 | | 44.39 | | |
| | | Bike Parking-Near Toilet | | | | | | | | | | |
| 0 | 15 | | Sqm | 1 | 15.00 | 9.40 | 9.40 | 9.40 | | 141.00 | | |
| 15 | 21.3 | | Sqm | 1 | 6.30 | 9.40 | 9.35 | 9.38 | | 59.06 | | |
| | | temple portion | | | | | | | | | | |
| 0 | 1.17 | | Sqm | 1 | 1.17 | 10.86 | 10.86 | 10.86 | | 12.71 | | |
| 1.17 | 14 | | Sqm | 1 | 12.83 | 13.88 | 12.68 | 13.28 | | 170.38 | | |
| 14 | 16 | | Sqm | 1 | 2.00 | 12.68 | 10.86 | 11.77 | | 23.54 | | |
| 16 | 20.4 | | Sqm | 1 | 4.40 | 10.86 | 13.16 | 12.01 | | 52.84 | | |
| 20.4 | 24.7 | | Sqm | 1 | 4.30 | 13.16 | 14.29 | 13.73 | | 59.02 | | |
| | | 16th B Cross Road | | | | | | | | | | |
| 0 | 15 | | Sqm | 1 | 15.00 | 5.00 | 5.00 | 5.00 | | 75.00 | | |
| 15 | 30 | | Sqm | 1 | 15.00 | 5.00 | 5.00 | 5.00 | | 75.00 | | |
| 30 | 45 | | Sqm | 1 | 15.00 | 5.00 | 5.00 | 5.00 | | 75.00 | | |
| 45 | 60 | | Sqm | 1 | 15.00 | 5.00 | 5.00 | 5.00 | | 75.00 | | |

| Chainage From | Chainage To | Description of Item | Unit | No | Length | Breadth B1 | Breadth B2 | Breadth Avg | Depth | Qty | Rate | Amount |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 60 | 75 | | Sqm | 1 | 15.00 | 5.00 | 5.05 | 5.03 | | 75.38 | | |
| 75 | 90 | | Sqm | 1 | 15.00 | 5.00 | 5.00 | 5.00 | | 75.00 | | |
| 90 | 105 | | Sqm | 1 | 15.00 | 5.00 | 9.00 | 7.00 | | 105.00 | | |
| | | 16th 'B' Cross Road | | | | | | | | | | |
| 0 | 15 | | Sqm | 1 | 15.00 | 5.95 | 5.95 | 5.95 | | 89.25 | | |
| 15 | 30 | | Sqm | 1 | 15.00 | 5.95 | 5.95 | 5.95 | | 89.25 | | |
| 30 | 37.6 | | Sqm | 1 | 7.60 | 5.95 | 5.95 | 5.95 | | 45.22 | | |
| | | Judicial Layout | | | | | | | | | | |
| 0 | 2.65 | | Sqm | 1 | 2.65 | 6.40 | 6.40 | 6.40 | | 16.96 | | |
| 2.65 | 17.65 | | Sqm | 1 | 15.00 | 4.90 | 4.90 | 4.90 | | 73.50 | | |
| 17.65 | 23.65 | | Sqm | 1 | 6.00 | 4.90 | 4.90 | 4.90 | | 29.40 | | |
| 23.65 | 25.45 | | Sqm | 1 | 1.80 | 6.00 | 6.00 | 6.00 | | 10.80 | | |
| | | Deduction | | | | | | | | | | |
| | | | Sqm | -1 | 2.10 | 1.90 | 1.90 | 1.90 | | -3.99 | | |
| | | Temple Portion | | | | | | | | | | |
| | | Public Toilet | Sqm | -1 | 7.82 | 12.20 | 12.20 | 12.20 | | -95.40 | | |
| | | 0 | Sqm | -1 | 3.65 | 5.50 | 5.50 | 5.50 | | -20.08 | | |
| | | Sump | Sqm | -1 | 3.44 | 1.22 | 1.22 | 1.22 | | -4.20 | | |
| | | Tree | Sqm | -1 | 0.90 | 0.60 | 0.60 | 0.60 | | -0.54 | | |
| | | Temple | Sqm | -1 | 4.00 | 5.94 | 5.94 | 5.94 | | -23.76 | | |
| | | | Sqm | -1 | 2.50 | 3.15 | 3.15 | 3.15 | | -7.88 | | |
| | | Borewell | Sqm | -1 | 1.20 | 1.00 | 1.00 | 1.00 | | -1.20 | | |
| | | Tree | Sqm | -1 | 1.10 | 1.00 | 1.00 | 1.00 | | -1.10 | | |
| | | Electic Pole | Sqm | -1 | 0.80 | 0.60 | 0.60 | 0.60 | | -0.48 | | |
| | | Bike Parking Lot | Sqm | -1 | 4.30 | 1.40 | 1.40 | 1.40 | | -6.02 | | |
| | | Door | Sqm | -1 | 2.54 | 0.87 | 0.87 | 0.87 | | -2.21 | | |
| | | Borewell | Sqm | -1 | 1.20 | 0.90 | 0.90 | 0.90 | | -1.08 | | |
| | | Chamber | Sqm | -2 | 1.00 | 0.70 | 0.70 | 0.70 | | -1.40 | | |
| | | | | | | | | | Total | 3470.44 | | |
| | | | | | | | | | Tender Quantity | 3246.71 | | |
| | | | | | | | | | Quantity Upto 125% | 3470.44 | 1233.67 | 4281384.00 |
| 27 | | Providing and fixing precast bollards made out of M30 ready mixed concrete laid in 15cm thick with steel reinforcement including form work, curing, including cost of all materials, labour, painting, HOM of machineries, loading, unloading, lead and lift, transportation etc.complete and as per the directions of the Engineer-in-charge of the work (Approved Data rate) | | | | | | | | | | |
| | | Near parking lot | Nos | 41 | | | | | | 41.00 | | |
| | | | | | | | | | Total | 41.00 | 1300.14 | 53306.00 |
| | | | | | | | | | Tender Quantity | 58.00 | | |
| | | | | | | | | | | | Total Amount | 18347750.00 |
| | | | | | | | | | | | GST Charges (12% of estimated cost) | 2201730.00 |
| | | | | | | | | | | | Grand Total Amount | 20549480.00 |

Assistant Engineer
BBMP

Assistant Executive Engineer
BBMP

Executive Engineer
BBMP

Technical Sanction
Accorded For Rs.20549480.00
Head of A/C P.3853.....
CER NO : 31..... Dt: 18.08.2022